

F. A. P. REC.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	05-00047-00-CH	WILL	036	004
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT #63033

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					I000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-1F	Y080
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	354	354						
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	137.5	137.5						
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2						
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2						
	63200310	GUARDRAIL REMOVAL	FOOT	287.5	287.5						
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
	67100100	MOBILIZATION	L SUM	1	1						
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1						
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	427	427						
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3915	3915						
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	69	69						
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1585	1585						
	72000100	SIGN PANEL - TYPE 1	SQ FT	7.5	7.5						
	72000200	SIGN PANEL - TYPE 2	SQ FT	25	25						
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9						
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2						
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8579	8579						
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	487	487						
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	92	92						
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	162	162						
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	122	122						
*	78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	72.8						
*	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	44	44						
*	78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	128	128						
*	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	28	28						
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	168	168						
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2						
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	461						461	
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	70						70	
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	5						5	
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	132						132	
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	154						154	
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	230						230	
*	81400100	HANDHOLE	EACH	2						2	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4						4	
*	81400300	DOUBLE HANDHOLE	EACH	1						1	
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	668						668	
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1						1	
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 3C	FOOT	505						505	
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 5C	FOOT	1886						1886	
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 7C	FOOT	283						283	
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.14 1 PAIR	FOOT	958						958	
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	120						120	
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1						1	
*	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1						1	
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1						1	
*	87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1						1	
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4						4	

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**IL RTE 53 AT UNIVERSITY PARKWAY
INTERSECTION IMPROVEMENT
SUMMARY OF QUANTITIES**

SCALE: VERT. NA
HORIZ. NA
DATE: 8-29-08

DRAWN BY: RG
CHECKED BY: WD

ROBINSON ENGINEERING, LTD.
1700 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 321-6700 FAX (708) 321-3828
ILLINOIS DESIGN FIRM REGISTRATION NO. 154001128

04161_02-QUAN-01