

ITEM NO	DESCRIPTION	UNIT	LOCATION	OFFSET	REMARKS
44200976	CLASS B PATCHES, TYPE IV, 10 INCH				
	<u>SQ YD</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	72	2123+83 TO 2124+08			
	165	2130+59 TO 2131+16			
	237	TOTAL			
44213200	SAW CUTS				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	103	2123+83 TO 2124+08			
	135	2130+59 TO 2131+16			
	238	TOTAL			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"				
	<u>SQ YD</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	903	2122+32 TO 2134+14	LT		
	874	2122+41 TO 2133+90	RT		
	1777	TOTAL			
50100300	REMOVAL OF EXISTING STRUCTURES NO.1				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1	2130+85.6			REMARKS 6' X 4' Box Culvert
50100400	REMOVAL OF EXISTING STRUCTURES NO.2				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1	2134+60.85	RT		REMARKS 15" CMP EXTENSION
50200400	ROCK EXCAVATION FOR STRUCTURES				
	<u>CU YD</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	23	2124+03			REMARKS USE IF APPLICABLE
51500100	NAME PLATES				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1	2124+03			REMARKS
52100510	ANCHOR BOLTS, 3/4"				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	8	2134+60.85			REMARKS 2 EACH WALL AT 24" CTS
54010505	PRECAST CONCRETE BOX CULVERTS 5'X5'				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	100	2124+03			REMARKS 2 CELLS @ 50'
	8	2124+03	LT		EXTENSION - Existing Structure 42'
	108	TOTAL			
542D0235	PIPE CULVERTS, CLASS D, TYPE 1, 30"				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	10	2134+60.85			REMARKS EXTEND 2' INSIDE EXISTING 3X3 PCC BOX *ESTIMATED QUANTITY
54215565	METAL END SECTIONS 30"				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1	2134+60.85	RT		REMARKS
54248510	CONCRETE COLLAR				
	<u>CU YD</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	0.75	2134+60.85	RT		REMARKS *ESTIMATED QUANTITY

ITEM NO	DESCRIPTION	UNIT	LOCATION	OFFSET	REMARKS
61100500	EXPLORATION TRENCH 52" DEPTH				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	100	2123+50 TO 2124+50	LT		
	100	2123+50 TO 2124+50	RT		
	200	TOTAL			
61100605	MISCELLANEOUS CONCRETE				
	<u>CU YD</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	0.22	2124+25	LT		REMARKS SLOPEWALL FOR FIELD TILE
63200310	GUARDRAIL REMOVAL				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	237.5	2122+59 TO 2124+98	RT		
	287.5	2122+94.2 TO 2125+84.2	LT		
	425	2129+19.7 TO 2133+45.2	LT		
	950	TOTAL			
63500105	DELINEATORS				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	2	2124+03	LT & RT		REMARKS
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1	2121+29	68.9' LT		
	1	2122+50	75' LT		
	1	2122+50	50.69' RT		
	1	2123+50	90' RT		
	1	2123+75	90' RT		
	1	2124+50	90' RT		
	1	2125+00	70' RT		
	1	2130+00	70' RT		
	1	2131+00	90' RT		
	1	2131+50	90' LT		
	1	2132+16	32.88' LT		
	1	2132+16	90' RT		
	1	2133+50	37.22' LT		
	1	2133+50	90' RT		
	1	2133+83	145.56' LT		
	1	2134+18	102.74' RT		
	16	TOTAL			
66700305	PERMANENT SURVEY MARKERS, TYPE II				
	<u>EACH</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	2	ENTIRE JOB			REMARKS CONTACT SURVEY DEPARTMENT
70300100	SHORT-TERM PAVEMENT MARKING				
	<u>FOOT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	4	2123+83 TO 2124+08	CL		YELLOW
	8	2123+83 TO 2124+08	EOP		WHITE
	4	2130+59 TO 2131+16	CL		YELLOW
	8	2130+60 TO 2131+17	EOP		WHITE
	24	TOTAL			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL				
	<u>SQ FT</u>	<u>LOCATION</u>		<u>OFFSET</u>	
	1.33	2123+83 TO 2124+08	CL		
	2.66	2123+83 TO 2124+08			
	1.33	2130+59 TO 2131+16	CL		
	2.66	2130+59 TO 2131+16			
	7.98	TOTAL			