

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL	80% Fed 20% Stat RDWY I000	50% STATE 50% CITY RDWY I000	100% CITY RDWY Y060	80% Fed 20% State MINOR STRUCTURE Y007
20200100	EARTH EXCAVATION	CU YD	3330				3330
	AND						
20201200	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	CU YD	145				145
* 25000100	SEEDING, CLASS 1	ACRE	0.25				0.25
* 25000210	SEEDING, CLASS 2A	ACRE	0.75				0.75
* 25000310	SEEDING, CLASS 4	ACRE	0.50				0.5
* 25000750	MOWING	ACRE	1				1
25100630	EROSION CONTROL BLANKET	SQ YD	5330				5330
25100900	TURF REINFORCEMENT MAT	SQ YD	352				352
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450				450
28000300	TEMPORARY DITCH CHECKS	EACH	24				24
28000400	PERIMETER EROSION BARRIER	FOOT	1909				1909
28000500	INLET AND PIPE PROTECTION	EACH	4				4
28100107	STONE RIPRAP, CLASS A4	SQ YD	69				69
28200200	FILTER FABRIC	SQ YD	69				69
35101400	AGGREGATE BASE COURSE, TYPE B	TON	267				267
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	100.6	100.6			
40600300	AGGREGATE (PRIME COAT)	TON	257	257			
40600525	LEVELING BINDER (HAND METHOD), N50	TON	54	54			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	9522	9522			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	1245	1245			

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = dossdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>	F.A.P. RTE. 654	SECTION *	COUNTY STEPHENSON	TOTAL SHEETS 89	SHEET NO. 5
cd\pwork\PWIDOT\DOSSDD\dms33571\d029677.dgn		DRAWN -	REVISED -			CONTRACT NO. 64C91				
PLOT SCALE = 52.9412' / 1" IN.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
PLOT DATE = Wed Sep 24 07:37:43 2008		DATE -	REVISED -		ILLINOIS FED. AID PROJECT					