

PATCHING SCHEDULE

13FOOT LANE WIDTH

7FOOT LANE WIDTH FOR 1/2 LANE PATCH

STATION	REMARKS	LENGTH OF PATCH		AREA OF CLASS B PATCHES, 14"								HMA REMOVAL OVER PATCHES 7"		HMA REPLACEMENT OVER PATCHES 7"			
		LT LANE (feet)	RT LANE (feet)	TYPE 1		TYPE 2		TYPE 3		TYPE 4		LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (tons)	RT LANE (tons)		
				LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)						
500 + 37		6				8.7							10.0		3.91		
504 + 45		6				8.7							10.0		3.91		
510 + 96			25								36.1		37.4			14.67	
511 + 60			8				11.6						12.9			5.04	
511 + 86		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
513 + 75		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
514 + 77			6				8.7						10.0			3.91	
516 + 42		25	25							36.1	36.1		37.4	37.4	14.67	14.67	
530 + 25		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
532 + 24		25	25							36.1	36.1		37.4	37.4	14.67	14.67	
539 + 20		6	15			8.7			21.7				10.0	23.0	3.91	9.00	
539 + 73		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
541 + 13			6				8.7						10.0			3.91	
547 + 24			20									28.9		30.2		11.83	
547 + 86			10				14.4							15.7		6.17	
548 + 75			100									144.4		145.7		57.13	
557 + 50		20								28.9			30.2		11.83		
558 + 49		15						21.7					23.0		9.00		
561 + 36		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
561 + 87		6				8.7							10.0		3.91	0.00	
562 + 2			50									72.2		73.5		28.82	
562 + 50		25								36.1			37.4		14.67		
563 + 23			6				8.7							10.0		3.91	
563 + 78		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
564 + 59		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
565 + 39		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
565 + 88			6				8.7							10.0		3.91	
567 + 49		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
568 + 48		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
568 + 85		6				8.7							10.0		3.91		
569 + 95		6	6			8.7	8.7						10.0	10.0	3.91	3.91	
570 + 80		28	6				8.7			40.4			41.7	10.0	16.36	3.91	
571 + 64		8	8			11.6	11.6						12.9	12.9	5.04	5.04	
573 + 48		6				8.7							10.0		3.91		
574 + 69		45	25							65.0	36.1		66.3	37.4	25.99	14.67	
577 + 87		26	26							37.6	37.6		38.9	38.9	15.23	15.23	
Total						1422.8	1521.0	257.1	338.0	2277.9	3466.7	4225.6	5636.4	1656.4	2209.5		
Expect to replace 5% +/- of total						71.1	76.1	25.7	33.8	113.9	173.3						
Grand Total						147.2		59.5		287.2		9861.9		3865.9			

FILE NAME =	USER NAME = dossed	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73	F.A.P. RTE. 654	SECTION *	COUNTY STEPHENSON	TOTAL SHEETS 89	SHEET NO. 28
ct\pwr_work\PWIDOT\DOSSDD\dms33571\d0297evr.dgn		DRAWN -	REVISED -							
		CHECKED -	REVISED -							
		DATE -	REVISED -							