

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE												
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 80% FEDERAL 20% STATE	STRUCTURE X371-5B 80% FEDERAL 20% STATE	ROADWAY 1000-2A 100% COUNTY	SIGNALS 1031-1F 80% FEDERAL 20% STATE	LIGHTING 1030-1E 80% FEDERAL 20% STATE								
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, No.18 3 PAIR	FOOT	1707.5				1707.5									
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	2				2									
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55FT.	EACH	2				2									
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5				3.5									
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56				56									
87900200	DRILL EXISTING HANDHOLE	EACH	2				1	1								
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAS T-ARM MOUNTED	EACH	7				7									
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRA CKET MOUNTED	EACH	1				1									
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAS T ARM MOUNTED	EACH	4				4									
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRA CKET MOUNTED	EACH	6				6									
88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLAS TIC	EACH	11				11									
88500100	INDUCTIVE LOOP DETECTOR	EACH	12				12									
88600100	DETECTOR LOOP, TYPE I	FOOT	1546				1546									
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1									
89502380	REMOVE EXISTING HANDHOLE	EACH	10				10									
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5				5									
Z0017202	DOWEL BARS 1 1/2"	EACH	2660	2660												
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIR ECTIVE), TEST LEVEL 3	EACH	1	1												
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY RED IRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1												
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1												
XX004093	CONCRETE SLOPEWALL REMOVAL	SO FT	7920		7920											
XX005703	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT . SPECIAL	L SUM	1				1									
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	591.4	591.4												
X0321583	PIPE ELBOW 18"	EACH	2	2												
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	6		6											

SPECIALTY ITEMS

FILE NAME c:\projects\hsm\hwy\misc.dgn	USER NAME = everasl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100:0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/28/2008	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.U. RTE. 6758	SECTION (1-R), (1-VC)BR	COUNTY PEORIA	TOTAL SHEETS 142	SHEET NO. 10
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68092	