

TREE REMOVAL, ACRES	
LOCATION	ACRE
LT STA 230+20 TO 44+40	0.3
SW CORNER IL 116/AIRPORT RD	0.9
TOTAL	1.2

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA 230+50 TO 43+70	122.5
STA 47+68 TO 49+70 AND ACCELERATION LANE	2177.3
SPUR LT STA 50+35 TO 51+00	26.7
TOTAL	2326.5

COMBINATION CURB & GUTTER REMOVAL	
LOCATION	FOOT
LT STA. 197+50 TO 201+50	400
RT STA. 197+50 TO 201+50	403
LT STA 202+33 TO 202+41	8
RT STA. 202+02 TO 202+20	35
RT STA 47+26 TO RT 241+81 (IL 116)	703
LT STA 47+34 TO RT 235+20 (IL 116)	220
RT STA 235+50 (IL 116) TO LT 51+27 (SPUR)	127
TOTAL	1896

APPROACH SLAB REMOVAL	
LOCATION	SQ YD
STA 43+70 TO 44+03	93.3
STA 46+42 TO 46+72	93.3
TOTAL	186.6

BITUMINOUS CONCRETE SHOULDER REMOVAL	
LOCATION	SQ YD
Airport Road	
LT STA 196+00 TO 205+50	316.7
LT STA 205+50 TO 207+50	222.2
LT STA 211+81 TO 216+06	141.5
LT STA 222+00 TO 225+70	411.1
LT STA 225+70 TO 230+36	163.4
LT STA 43+70 TO 43+86	17.8
RT STA 200+00 TO 201+00	139.3
RT STA 202+10 TO 203+00	268.8
RT STA 43+47 TO 43+77	60.7
LT STA 43+47 TO 43+77	52.4
IL 116	
RT STA 231+80 TO 235+51	329.8
LT STA 235+10 TO 235+87	68.4
Kickapoo Creek Spur	
LT STA 52+22 TO 53+91	75.1
TOTAL	2267.2

GUTTER OUTLET REMOVAL	
LOCATION	EACH
RT STA 235+45 (IL 116)	1
RT STA 235+84 (IL 116)	1
RT STA 238+95 (IL 116)	1
RT STA 51+18 (SPUR)	1
TOTAL	4

PAVED DITCH REMOVAL	
LOCATION	FOOT
RT STA. 227+00 TO 227+16	16
RT STA. 227+58 TO 227+78	20
TOTAL	36

ISLAND REMOVAL	
LOCATION	SQ FT
AIRPORT RD / IL 116 INTERSECTION	
NORTHWEST CORNER ISLAND	225
SOUTHWEST CORNER ISLAND	435
SOUTHEAST CORNER ISLAND	1150
TOTAL	1810

MEDIAN REMOVAL	
LOCATION	FOOT
STA 201+40 TO 201+50	10
IL 116 STA 233+70 TO 236+40	270
IL 116 STA 237+25 TO 239+00	175
TOTAL	455

REMOVING INLETS	
LOCATION	EACH
LT STA 230+18	1
RT STA 49+87 OFFSET 83.9'	1
TOTAL	2

STEEL PLATE BEAM GUARDRAIL REMOVAL	
LOCATION	FOOT
LT STA 196+00 TO 207+46	1150
LT STA 211+91 TO 216+06	412.5
LT STA 222+67 TO 230+20	750
RT STA 205+21 TO 206+87	175
RT STA 43+30.6 TO 44+07	75
LT STA 47+34 TO LT 48+34	100
RT STA 47+68 TO RT 241+81 (IL 116)	685
TOTAL	3347.5

CONCRETE SHOULDER CURB	
LOCATION	FOOT
LT STA 230+10 TO 230+25	15
TOTAL	15

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
AIRPORT RD (BRIDGE TO IL 116)	16
IL 116 AND KICK CR. SPUR	47
TOTAL	63

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
TOTAL SEEDING = 1.64 ACRES 100 POUNDS PER ACRE	
TOTAL	164
X 2 APPLICATIONS	
TOTAL	328

TEMPORARY DITCH CHECKS	
LOCATION	EACH
LT STA 51+50 (SPUR)	1
LT STA 51+75 (SPUR)	1
LT STA 52+00 (SPUR)	1
LT STA 52+25 (SPUR)	1
LT STA 52+50 (SPUR)	1
LT STA 52+75 (SPUR)	1
LT STA 53+00 (SPUR)	1
LT STA 53+25 (SPUR)	1
LT STA 53+50 (SPUR)	1
LT STA 53+75 (SPUR)	1
LT STA 54+00 (SPUR)	1
SUBTOTAL	11
X 2 APPLICATIONS	
TOTAL	22

PERIMETER EROSION BARRIER	
LOCATION	FOOT
STA 235+00 TO 44+25	107
STA 197+50 TO 201+40	390
RT STA 232+87 TO RT STA 234+14	242
RT STA 46+88 TO RT STA 47+95	125
SUBTOTAL	864
X 2 APPLICATIONS	
TOTAL	1728

AGGREGATE BASE CSE, TYPE B	
LOCATION	TON
LT. STA. 196+30 TO 201+40	34.5
RT. STA. 196+30 TO 201+40	29.3
TOTAL	63.8

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1

BRIDGE APPROACH PAVEMENT	
LOCATION	SQ YD
STA. 43+47 TO 43+77	216.7
STA 47+07 TO 47+37	216.7
TOTAL	433.4

BRIDGE APPROACH PAVEMENT CONNECTOR	
LOCATION	SQ YD
STA. 230+50 TO 43+47	260
STA 47+37 TO 47+43	37.3
TOTAL	297.3

PAVED DITCH (SPECIAL)	
LOCATION	FOOT
RT STA. 227+00 TO 227+16	16
RT STA. 227+58 TO 227+78	20
TOTAL	36

METAL END SECTIONS 18"	
LOCATION	EACH
LT STA 230+18	1
TOTAL	1

PIPE ELBOW 18"	
LOCATION	EACH
LT STA 230+18	1
LT STA 230+18	1
TOTAL	2

INLETS, TYPE G-1	
LOCATION	EACH
RT STA 49+89 OFFSET 63.2'	1
TOTAL	1

FRAMES AND LIDS TO BE ADJUSTED	
LOCATION	EACH
STA 208+07	1
STA 208+25	1
STA 214+25	1
STA 216+70	1
STA 228+17	1
STA 229+10	1
TOTAL	6

FRAMES AND GRATES TO BE ADJUSTED	
LOCATION	EACH
Lt. Sta. 202+40	1
Lt. Sta. 214+50	1
TOTAL	2

FILE NAME =	USER NAME = everscl	DESIGNED -	REVISED -
C:\Documents and Settings\everscl\Desktop\Harmon Highway\misc.dgn		DRAWN -	REVISED -
REvised 11/2008		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

Schedule of Quantities			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6758	(I-R),(I-VC)BR	PEORIA	142	17
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 68092	