

SHOULDER RESURFACING AND REPLACEMENT TABLE												
LOCATION		LENGTH	WIDTH	AREA	HMA SURFACE REMOVAL 2"	HMA SHOULDERS			HMA SHOULDERS 8"	HMA SHOULDERS 10"	AGGREGATE SHOULDERS TYPE B	
						2"	4.5"	Var			8"	VAR
AIRPORT ROAD WB		FEET	FEET	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	TON	TON
Sta. 196+00	to	Sta. 205+50	950	7.4	781.1	781.1	43.5	113.9	110.5		389	
Sta. 205+50	to	Sta. 206+50	100	7.4	82.2		9.2			82.2		
Sta. 206+50	to	Sta. 207+50	100	10	111.1		12.4			111.1		
Sta. 207+50	to	Sta. 211+81	431	10	478.9	478.9		120.7			65.4	
Sta. 211+81	to	Sta. 216+06	424.6	7.4	349.1	349.1		88				
Sta. 216+06	to	Sta. 222+00	594.4	10	660.4	660.4		166.4			90.3	
Sta. 222+00	to	Sta. 222+54	53.5	10	59.4		6.7			59.4	8.1	
Sta. 222+54	to	Sta. 225+70	316.5	7.4	260.2		29.1			260.2		
Sta. 225+70	to	Sta. 229+71	401	7.4	329.7	329.7		83.1				
Sta. 229+71	to	Sta. 230+36	65	VAR	50.6	50.6		12.8	9.1		9.9	
AIRPORT ROAD EB												
Sta. 196+00	to	Sta. 200+07	407	10	452.2	452.2		114			61.8	
Sta. 200+07	to	Sta. 203+20	313									
Sta. 203+20	to	Sta. 214+50	1130	10	1255.6	1255.6		316.4			171.6	
Sta. 214+50	to	Sta. 228+50	1400	10	1555.6	1555.6		286.7				
Sta. 228+50	to	Sta. 229+55	105	10	116.7	116.7		29.4				
Sta. 229+55	to	Sta. 230+14	59	10	65.6	65.6		16.5			9	
Sta. 230+14	to	Sta. 230+53	39.23	VAR	34.9	34.9		8.8			6	
Sta. Eqn. 230+53.2 (BK) = 43+14.12 (AH)												
Sta. 43+14	to	Sta. 43+34	19.48	VAR	10.8	10.8		2.7			3	
IL116												
RT Sta. 231+80	to	Sta. 233+06	126	8	112.0				112.0			
LT Sta. 231+80	to	Sta. 235+10	330	8	293.3	293.3	32.8					
RT Sta. 235+10	to	Sta. 235+75	65	8	57.8				57.8			
KICKAPOO CR. SPUR ROAD												
RT Sta. 51+53	to	Sta. 54+58	305	4	135.6			50.1			16.3	
RT Sta. 54+58	to	Sta. 57+52	294	4	130.7		14.6					
LT Sta. 53+85	to	Sta. 54+58	73	VAR	64.9			13.8				
LT Sta. 54+58	to	Sta. 57+96	338	4	150.2		16.8					
SUBTOTALS							165.1	1359.4	183.5		425.1	16.3
TOTALS					6434.5		1708		169.8	901.9	441.4	

FILE NAME *	USER NAME = everscl	DESIGNED -	REVISED -
C:\Documents and Settings\everscl\Desktop\Harmon Highway\misc.dgn		DRAWN -	REVISED -
Revised 11/208	PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/17/2000	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6758	(I-RI),(I-VC)BR	PEORIA	142	21
FED. ROAD DIST. NO.			CONTRACT NO. 68092	
ILLINOIS FED. AID PROJECT				