

TREE REMOVAL, ACRES		
Location	UNIT	Qty.
Rt. Sta. 536+05 to Rt. Sta. 538+82.43	ACRE	0.28
TOTAL = 0.28		

TOPSOIL FURNISH AND PLACE, 4"		
Location	UNIT	Qty.
Rt. Sta. 536+00 to Rt. Sta. 538+75	SQ YD	796
TOTAL = 796		

STONE RIPRAP CLASS A4		
Location	UNIT	Qty.
Rt. Sta. 537+64.31 to Rt. Sta. 537+73.53	TON	6.5
TOTAL = 6.5		

EARTH EXCAVATION		
Location	UNIT	Qty.
Rt. Sta. 536+00 to Rt. Sta. 538+75	CU YD	256
TOTAL = 256		

SEEDING, CLASS 3		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 538+81.57	ACRE	0.25
TOTAL = 0.25		

FILTER FABRIC		
Location	UNIT	Qty.
Rt. Sta. 537+64.31 to Rt. Sta. 537+73.53	SQ YD	8.5
TOTAL = 8.5		

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		
Location	UNIT	Qty.
Rt. Sta. 536+68.90	CU YD	42
TOTAL = 42		

NITROGEN FERTILIZER NUTRIENTS		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 538+81.57	POUND	23
TOTAL = 23		

FABRIC FORMED CONCRETE PAVEMENT MAT		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 537+64.31	SQ YD	227.00
Rt. Sta. 537+73.53 to Rt. Sta. 5387+68.82		214.00
TOTAL = 441		

FURNISHED EXCAVATION		
Location	UNIT	Qty.
Rt. Sta. 536+00 TO Rt. Sta. 538+75	CU YD	415
TOTAL = 415		

PHOSPHORUS FERTILIZER NUTRIENTS		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 538+81.57	POUND	23
TOTAL = 23		

CONSTRUCTION TEST STRIP		
Location	UNIT	Qty.
JOBSITE	EACH	2
TOTAL = 2		

POROUS GRANULAR EMBANKMENT		
Location	UNIT	Qty.
Rt. Sta. 537+68.90	CU YD	4
TOTAL = 4		

POTASSIUM FERTILIZER NUTRIENTS		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 538+81.57	POUND	23
TOTAL = 23		

CURB REMOVAL		
Location	UNIT	Qty.
Rt. Sta. 536+28.68 to Rt. Sta. 538+43.49	FOOT	215
TOTAL = 215		

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		
Location	UNIT	Qty.
Rt. Sta. 537+68.90	SQ YD	22
TOTAL = 22		

HEAVY DUTY EROSION CONTROL BLANKET		
Location	UNIT	Qty.
Rt. Sta. 536+24.90 to Rt. Sta. 538+81.57	SQ YD	796
TOTAL = 796		

PAVED SHOULDER REMOVAL		
Location	UNIT	Qty.
Rt. Sta. 536+28.68 to Rt. Sta. 538+43.49	SQ YD	130
TOTAL = 130		

FILE NAME =	USER NAME = brucebm	DESIGNED -	REVISED -
S:\GEN\DRAW\STD&PLNS\SOJAD11\68337\68	37A\plans.dgn	DRAWN -	REVISED -
	PLOT SCALE = 44.2009' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/14/2008	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. 317	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
US24	(137,102)RS-4; 101RS-3	FULTON	12	12
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 68337	