

SUMMARY OF QUANTITIES-FOR INFORMATIONAL PURPOSE ONLY

CONTRACT NO. 68573			
F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS
253	68 BR-1	MARSHALL	97 63
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	

S.P.	PAY ITEM CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY RESURFACING	BRIDGE
					1000-2A	X071-2A
	20200100	EARTH EXCAVATION	CU YD	1,070	1,070	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	92	92	
	20300100	CHANNEL EXCAVATION	CU YD	365		365
	20400800	FURNISHED EXCAVATION	CU YD	170	170	
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	97		97
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,081	5,081	
	25000210	SEEDING, CLASS 2A	ACRE	1	1	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	95	95	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	95	95	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	95	95	
	25100115	MULCH, METHOD 2	ACRE	1	1	
	25100630	EROSION CONTROL BLANKET	SQ YD	5,402	5,402	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	112	112	
	28000300	TEMPORARY DITCH CHECKS	EACH	9	9	
	28000400	PERIMETER EROSION BARRIER	FOOT	3,574	3,574	
	28100807	STONE DUMPED RIPRAP, CLASS A4	TON	820		820
	28200200	FILTER FABRIC	SQ YD	891		891
	35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	254	254	
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
	40600300	AGGREGATE (PRIME COAT)	TON	1	1	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	517	517	
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,454	1,454	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	233	233	
	42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222		222
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	40		40
	44000100	PAVEMENT REMOVAL	SQ YD	300	300	
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	9	9	
	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1
	50200100	STRUCTURE EXCAVATION	CU YD	335		335
	50300100	FLOOR DRAINS	EACH	8		8
	50300225	CONCRETE STRUCTURES	CU YD	30.4		30.4
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	111.8		111.8
	50300260	BRIDGE DECK GROOVING	SQ YD	257		257
	50300280	CONCRETE ENCASEMENT	CU YD	4.8		4.8
	50300300	PROTECTIVE COAT	SQ YD	339		339
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
	50500505	STUD SHEAR CONNECTORS	EACH	1,026		1,026
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	25,580		25,580
	50800515	BAR SPLICERS	EACH	64		64
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	336		336
	51202305	DRIVING PILES	FOOT	336		336
	51203600	TEST PILE STEEL HP12X53	EACH	2		2

S.P.	PAY ITEM CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY RESURFACING	BRIDGE
					1000-2A	X071-2A
	51204650	PILE SHOES	EACH	14		14
	51500100	NAME PLATES	EACH	1		1
	52100520	ANCHOR BOLTS, 1"	EACH	24		24
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66		66
	60109580	PIPE UNDERDRAINS FOR STRUCTURE 4"	FOOT	134		134
	63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,024	1,024	
	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
	63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4	
	63200310	GUARDRAIL REMOVAL	FOOT	1,329	1,329	
	66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	904	904	
	66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1		1
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.5	3.5	
	67100100	MOBILIZATION	L SUM	0.5	0.5	
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	0.5	0.5	
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15		15
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	160	160	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	80	80	
	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,823	1,823	
	78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	225	225	
	78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	33	33	
	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
	X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	399	399	
	X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	0.5	0.5	
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	0.5	0.5	
	Z0076600	TRAINEES	HOUR	250		250

REVISIONS	
NAME	DATE
C. MAUSHARD	9/5/08

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 ILL. RTE. 251
 OVER SANDY CREEK
 F.A.S. 253 SEC. 68 BR-1
 MARSHALL COUNTY
 STA. 133+80.00 S.N. 062-0085
 DESIGNED BY: A.G. DRAWN BY: T.C.S.
 DATE: 05/02/2008 CHECKED BY: O.A.O.