

SUMMARY OF QUANTITIES

100% STATE SFTY - 2A
HENDERSON

CODE NO.	ITEM	UNIT	RURAL	TOTAL
70400100	TEMPORARY CONCRETE BARRIER	FOOT	654	654
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	430	430
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1165	1165
78300100	PAVEMENT MARKING REMOVAL	SQFT	388	388
X0301424	SILICONE JOINT SEALER	FOOT	132	132
X0320047	REMOVAL OF EXISTING <i>← PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS	SQFT	2408	2408
X0320887	POLYMER CONCRETE	CUFT	34.3	34.3
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEM

SN. 036-0028 US. 34
over S.Henderson Crk.

FILE NAME = SN. 036-0028	USER NAME = #USER#	DESIGNED - ----	REVISED - ----
*FILE: S:\GEN\DRFT\TSDS\PLNS\SQUAD14		DRAWN - ----	REVISED - ----
NBRIDGE CONTRACTS\Emergency PPC Beam	PLOT SCALE = #SCALE#	CHECKED - ----	REVISED - ----
Repair#68849 SN.036-0028 S.Henderson	PLOT DATE = #DATE#	DATE - ----	REVISED - ----
Crk.dgn			

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	(GBR-1)I	HENDERSON	4	4
EMERGENCY BEAM REPLACEMENT		CONTRACT NO. 68849		
FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT				