

SUMMARY OF QUANTITIES


URBAN
80% FED
20% STATE

YO31-1F

SFTY-1A

A000-1A

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	TRAFFIC SIGNALS	PEDESTRIAN RAMPS	CHANNELIZATION
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	FOOT	10.0			10.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	248.0			248.0
67100100	MOBILIZATION	L SUM	1.0	0.2	0.4	0.4
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.2	0.2	0.6
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	0.2	0.6	0.2
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	400.0			400.0
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	112.0			112.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	526.0			526.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120.0			120.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	422.0			422.0
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	4.0	4.0		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4.0	4.0		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	12.0	12.0		
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1.0	1.0		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10.0	10.0		
87900200	DRILL EXISTING HANDHOLE	EACH	1.0	1.0		



Rev. 12-30-08

*Specialty Items

Rev.

FILE NAME =	USER NAME = laughlrr1	DESIGNED -	REVISED -
ct:\pw\work\VPWIDOT\LAUGHLINRL\dms20392\...	tsaoq.dgn	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Oct-15-2008 11:18:14AM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
63	78-2(ITS-2,N,T,I)	ADAMS	16	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72B72	