

SUMMARY OF QUANTITIES

URBAN
80% FED
20% STATE Y031-1F SFTY-1A A000-1A

<u>PAYCODE</u>	<u>ITEM DESCRIPTION</u>	<u>UNIT</u>	<u>TOTAL QUANTITIES</u>	<u>TRAFFIC SIGNALS</u>	<u>PEDESTRIAN RAMPS</u>	<u>CHANNEL-IZATION</u>
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2.0	2.0		
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1.0	1.0		
88040330	SIGNAL HEAD , POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1.0	1.0		
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2.0	2.0		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	3.0	3.0		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8.0	8.0		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	73.0	73.0		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.0	1.0		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1.0	1.0		
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	343.5	343.5		
X8950200	REBUILD EXISTING HANDHOLE	EACH	2.0	2.0		
XX001244	RETAINING WALL	FOOT	17.0		17.0	
XX003313	REMOVE AND REINSTALL BRICK PAVER	SQ FT	114.0			114.0



Rev. 12-30-08

