

SUMMARY OF QUANTITIES

| PAYCODE | ITEM DESCRIPTION | UNIT | URBAN 80% FED 20% STATE | | | |
|------------|--|-------|-------------------------------|---------|---------|---------|
| | | | TOTAL QUANTITIES | YO31-1F | SFTY-1A | A000-1A |
| 60609100 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG) | FOOT | 10.0 | | | 10.0 |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 248.0 | | | 248.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 | 0.2 | 0.4 | 0.4 |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1.0 | 0.2 | 0.2 | 0.6 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1.0 | 0.2 | 0.6 | 0.2 |
| 70300230 | TEMPORARY PAVEMENT MARKING - LINE 5" | FOOT | 400.0 | | | 400.0 |
| * 78000300 | * THERMOPLASTIC PAVEMENT MARKING - LINE 5" | FOOT | 112.0 | | | 112.0 |
| * 78000400 | * THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 526.0 | | | 526.0 |
| * 78000650 | * THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 120.0 | | | 120.0 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 422.0 | | | 422.0 |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 4.0 | 4.0 | | |
| 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 4.0 | 4.0 | | |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 12.0 | 12.0 | | |
| 87700180 | STEEL MAST ARM ASSEMBLY AND POLE, 28 FT. | EACH | 1.0 | 1.0 | | |
| 87800400 | CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 10.0 | 10.0 | | |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 1.0 | 1.0 | | |



Rev. 12-30-08 *Specialty Items Rev.

SUMMARY OF QUANTITIES

URBAN
80% FED
20% STATE Y031-1F SFTY-1A A000-1A

| PAYCODE | ITEM DESCRIPTION | UNIT | TOTAL QUANTITIES | TRAFFIC SIGNALS | PEDESTRIAN RAMPS | CHANNEL-IZATION |
|----------|--|-------|------------------|-----------------|------------------|-----------------|
| 88040090 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 2.0 | 2.0 | | |
| 88040230 | SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 1.0 | 1.0 | | |
| 88040330 | SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED | EACH | 1.0 | 1.0 | | |
| 88102830 | PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED | EACH | 2.0 | 2.0 | | |
| 88200100 | TRAFFIC SIGNAL BACKPLATE | EACH | 3.0 | 3.0 | | |
| 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 8.0 | 8.0 | | |
| 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 73.0 | 73.0 | | |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1.0 | 1.0 | | |
| 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 1.0 | 1.0 | | |
| X0323153 | ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN) | FOOT | 343.5 | 343.5 | | |
| X8950200 | REBUILD EXISTING HANDHOLE | EACH | 2.0 | 2.0 | | |
| XX001244 | RETAINING WALL | FOOT | 17.0 | | 17.0 | |
| XX003313 | REMOVE AND REINSTALL BRICK PAVER | SQ FT | 114.0 | | | 114.0 |



Rev. 12-30-08

