

SUMMARY OF QUANTITIES

URBAN
80% FED
20% STATE

YO31-1F

SFTY-1A

A000-1A

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	TRAFFIC SIGNALS	PEDESTRIAN RAMPS	CHANNELIZATION
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	FOOT	10.0			10.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	248.0			248.0
67100100	MOBILIZATION	L SUM	1.0	0.2	0.4	0.4
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.2	0.2	0.6
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	0.2	0.6	0.2
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	400.0			400.0
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	112.0			112.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	526.0			526.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120.0			120.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	422.0			422.0
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	4.0	4.0		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4.0	4.0		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	12.0	12.0		
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1.0	1.0		
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10.0	10.0		
* 87900200	DRILL EXISTING HANDHOLE	EACH	1.0	1.0		

*Specialty Items Rev.

FILE NAME =	USER NAME = laughlinc1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or\pwwork\pwwid007\LAUGHLINRL\dms20392\tssoq.dgn	DRAWN -	REVISED -	63			78-2(ITS-2,N,T,D)	ADAMS	16	4	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. T2B72							
PLOT DATE = Oct-15-2008 11:18:44AM	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	