



POINT	STATION	OFFSET (LT)	ELEVATION
1	10+23.70	40.70	585.79
2	10+24.50	35.63	586.02
3	10+25.73	33.89	586.11
4	10+30.77	31.53	586.31
5	10+25.75	35.66	586.08
6	10+28.68	40.80	586.27
7	10+30.87	37.07	586.33
8	10+32.99	37.05	586.35
9	10+33.03	41.10	586.35
10	10+31.07	46.12	586.73
11	10+45.01	39.27	587.35

* CURB ACCORDING TO STANDARD 424001 TYPE A EXCEPT CURB WIDTH SHALL BE 5" & VAR.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NE QUADRANT DETAILS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\PWIDOT\LAUGHLINRL\dms20392\hstdetail.dgn		DRAWN -	REVISED -		63	78-2(ITS-2,N,T,I)	ADAMS	16	9				
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 72B72				
	PLOT DATE = Oct-10-2008 09:54:04AM	DATE -	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT						