

CONTRACT NO. 72C25

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
723		MONTGOMERY	4	2
STA. 5+09		TO STA. 374+69		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
(16R)RS-7; (17R)RS-7				

NOKOMIS BLACKTOP
100% STATE
CONST. CODE F000

Code No.	Item	Unit	Total	
67100100	MOBILIZATION	L SUM	1.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4270.0	4270.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1423.0	1423.0
*78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	106,743	106,743
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	534	534
X0320217	TEMPORARY <i>RAISED</i> PAVEMENT MARKER	EACH	2135	2135
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	534	534
X0324951	CAPE SEAL	SQ YD	104,370	104,370

PLOT DATE = 04-18-2008 08:45:07
 FILE NAME = c:\pwork\p1007\LAKE\LINE\LAKE587A\SH4510.dwg
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlinr1

Rev.

* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAS 723
SECTION (16R)RS-7; (17R)RS-7
MONTGOMERY COUNTY
SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY: