

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODES	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAI 72 ROADWAY 4 LANE 90% FED 10% STATE I000
20200100	EARTH EXCAVATION	CU YD	1268	1268
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.81	0.81
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	81	81
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SO YD	4322	4322
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19053	19053
40600300	AGGREGATE (PRIME COAT)	TON	380	380
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	44	44
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	71	71
40600990	TEMPORARY RAMP	SO YD	800	800
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	13890	13890
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	9541	9541
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	68415	68415
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	960	960
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	111145	111145
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	4078	4078
44004250	PAVED SHOULDER REMOVAL	SO YD	3448	3448
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SO YD	518	518
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	904	904
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SO YD	189	189
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	460	460
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SO YD	2413	2413
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SO YD	41	41
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SO YD	18	18
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	85	85
44213000	PATCHING REINFORCEMENT	SO YD	3644	3644
44213100	PAVEMENT FABRIC	SO YD	18	18
44213200	SAW CUTS	FOOT	10595	10595
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1352	1352

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODES	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAI 72 ROADWAY 4 LANE 90% FED 10% STATE I000
48203043	HOT-MIX ASPHALT SHOULDERS, 11 1/2"	SO YD	3507	3507
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5992	5992
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	42	42
60500310	FILLING INLETS, SPECIAL	EACH	8	8
63500105	DELINEATORS	EACH	175	175
64200105	SHOULDER RUMBLE STRIP	FOOT	75717	75717
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29208	29208
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1305	1305
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1305	1305
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	81483	81483
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	10246	10246
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1687	1687
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1078	1078
⊙ X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	122	122
X0322729	MATERIAL TRANSFER DEVICE	TON	22146	22146
X0323644	PAVEMENT MARKING GROOVING	FOOT	128.5	128.5
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	3	3
X4401705	PARTIAL DEPTH REMOVAL	SO YD	848	848
X4421000	PARTIAL DEPTH PATCHING	TON	143	143
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
Z0017100	DOWEL BARS	EACH	120	120
Z0075300	TIE BARS	EACH	197	197

⊙ NON-PARTICIPATING
* Specialty Items