

PAVING SCHEDULE  
(MAINLINE)

PAVEMENT						BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N105	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, 1L-19.0, N105	HOT MIX ASPHALT SHOULDERS	HOT MIX ASPHALT SHOULDERS, 1 1/2"	HOT MIX ASPHALT REMOVAL, 1"	HOT MIX ASPHALT REMOVAL, 1 1/2"	HOT MIX ASPHALT REMOVAL, 3 1/4"	HOT MIX ASPHALT REMOVAL, VARIABLE DEPTH	TEMPORARY RAMP	AGGREGATE SHOULDERS, TYPE B
STATION	TO	STATION	LENGTH FEET	WIDTH FEET	AREA SQ YD												
700+98.00	TO	718+03.15	1,705.1	24.0	9,094.1	1,515.7	30.3	763.9	1,145.9	509.3	71.2	5,946.9		9,094.1	137.8	106.6	91.9
718+03.15	TO	719+00.65	97.5	24.0	520.0	86.7	1.7	43.7	43.7	29.1	107.1	44.5		520.0	595.0	106.6	5.3
719+00.65	TO	723+18.90	418.3	24.0	2,230.7	0.0	0.0	0.0	0.0	0.0	50.5				248.7		0.0
723+18.90	TO	724+16.40	97.5	24.0	520.0	86.7	1.7	43.7	43.7	29.1	271.8			520.0	638.8	106.6	5.3
724+16.40	TO	737+00.00	1,283.6	24.0	6,845.9	1,141.0	22.8	575.1	862.6	383.4	173.0	4,371.7		6,845.9	112.9		69.2
737+00.00	TO	745+41.90	841.9	24.0	4,490.1	748.4	15.0	377.2	565.8	251.4		2,058.0		4,490.1			45.4
745+41.90	TO	751+44.00	602.1	24.0	3,211.2	535.2	10.7	269.7	404.6	123.6		2,140.7		3,211.2			32.5
751+44.00	TO	752+73.44	129.4	24.0	690.3	115.1	2.3	58.0	87.0	38.7		460.2		690.3			7.0
752+73.44	TO	763+00.00	1,026.6	24.0	5,475.0	912.5	18.2	459.9	689.8	306.6		3,650.1		5,475.0			55.3
763+00.00	TO	766+22.02	322.0	24.0	1,717.4	286.2	5.7	144.3	216.4	96.2		787.2		1,717.4			17.4
766+22.02	TO	769+19.96	297.9	24.0	1,589.0	264.8	5.3	133.5	200.2	61.2		1,059.3		1,589.0			16.1
769+19.96	TO	770+75.06	155.1	24.0	827.2	137.9	2.8	69.5	104.2	46.3		551.5		827.2			8.4
770+75.06	TO	773+41.84	266.8	24.0	1,422.8	237.1	4.7	119.5	179.3	79.7		948.6		1,422.8			14.4
773+41.84	TO	777+00.00	358.2	24.0	1,910.2	318.4	6.4	160.5	240.7	107.0		875.6		1,910.2			19.3
777+00.00	TO	778+31.00	131.0	24.0	698.7	116.4	2.3	58.7	88.0	39.1		465.6		698.7			7.1
778+31.00	TO	781+71.28	340.3	24.0	1,814.8	302.5	6.0	152.4	228.7	101.6		1,058.8		1,814.8			18.3
781+71.28	TO	792+00.00	1,028.7	24.0	5,486.5	914.4	18.3	460.9	691.3	211.2		2,514.0		5,486.5			55.5
792+00.00	TO	796+30.35	430.4	24.0	2,295.2	382.5	7.7	192.8	289.2	128.5	212.1	1,784.6		2,295.2	286.4		23.2
796+30.35	TO	797+27.85	97.5	24.0	520.0	86.7	1.7	43.7	43.7	29.1	200.1			520.0	450.6	186.6	5.3
797+27.85	TO	801+07.85	380.0	24.0	2,026.7	0.0	0.0	0.0	0.0	0.0	208.9				161.8		0.0
801+07.85	TO	802+05.35	97.5	24.0	520.0	86.7	1.7	43.7	43.7	29.1	173.3			520.0	386.5	186.6	5.3
802+05.35	TO	841+87.88	3,982.5	24.0	21,240.2	3,540.0	70.8	1,784.2	2,676.3	1,189.4	346.2	13,387.9		21,240.2	126.0		214.7
841+87.88	TO	844+27.88	240.0	24.0	1,280.0	213.3	4.3	107.5	161.3	71.7		853.4		1,280.0			12.9
844+27.88	TO	852+80.56	852.7	24.0	4,547.6	757.9	15.2	382.0	573.0	254.7	108.0	2,717.8		4,547.6			46.0
852+80.56	TO	853+47.99	67.4	24.0	359.6	59.9	1.2	30.2	0.0	0.0	185.3			359.6	220.8		7.3
853+47.99	TO	854+00.38	52.4	24.0	279.4	46.6	0.9	23.5	0.0	0.0	197.2		132.2	0.0	18.2		5.6
854+00.38	TO	855+80.24	179.9	24.0	959.3	159.9	3.2	80.6	0.0	0.0	692.7		690.8	0.0	447.3		19.4
855+80.24	TO	856+32.74	52.5	24.0	280.0	46.7	0.9	23.5	0.0	0.0	200.2		137.0	0.0	18.7		5.7
856+32.74	TO	857+00.40	67.7	24.0	360.9	60.1	1.2	30.3	0.0	0.0	178.1	120.3		360.9	228.2		7.3
857+00.40	TO	881+71.44	2,471.0	24.0	13,178.9	2,196.5	43.9	1,107.0	1,660.5	738.0	131.0	8,785.6		13,178.9			133.2
881+71.44	TO	884+11.44	240.0	24.0	1,280.0	213.3	4.3	107.5	161.3	71.7		853.4		1,280.0			12.9
884+11.44	TO	910+00.00	2,588.6	24.0	13,805.7	2,300.9	46.0	1,159.7	1,739.5	773.1		9,071.9		13,805.7		106.6	139.5
SHEET TOTALS			20,902		111,477	17,870	357	9,006	13,140	5,699	3,507	64,508	960	105,701	4,078	800	1,107

FILE NAME =	USER NAME = swortzr	DESIGNED - JLD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\PW\DOT\SW\ARTZRW\dms35509\sh	sch_74171.dgn	DRAWN - RWS	REVISED -		72	(58,74)(66,67)RS-1	MACON	38	8			
PLOT SCALE = 20,000' / 1" IN.	CHECKED - WES	REVISED -	REVISED -		SCALE: NA SHEET NO. 1 OF 7 SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = 10/9/2008	DATE - 10-07	REVISED -	REVISED -					CONTRACT NO. 74171				