

TREE REMOVAL SCHEDULE				
LOCATION			DIAMETER (UNITS)	
STATION	OFFSET	SIDE	6" TO 15"	OVER 15"
2045+82.47	45.29	RT	8	
2045+83.49	44.72	RT	8	
2045+83.93	29.64	RT	14	
2046+00.82	44.43	RT	7	
2046+00.83	39.18	LT	12	
2046+08.11	27.01	RT	10	
2046+12.42	32.30	RT	8	
2046+13.31	47.82	RT	8	
2046+14.54	34.31	RT	7	
2046+16.45	43.75	RT	8	
2046+16.82	48.26	RT	8	
2046+25.82	40.28	LT	12	
2046+27.95	40.84	LT	12	
2046+29.71	46.54	RT	12	
2046+32.67	37.28	RT	10	
2046+32.72	37.29	RT	10	
2046+34.78	46.17	LT	6	
2046+37.80	47.27	LT	6	
2046+43.31	53.29	LT	6	
2046+52.47	41.29	RT	6	
2046+53.40	47.82	RT	14	
2046+58.56	48.15	LT	6	
2046+59.08	40.04	LT	9	
2046+60.59	38.67	LT	12	
2046+77.30	40.43	LT		16
2046+83.92	46.52	RT		18
2046+88.55	48.02	RT	9	
2047+08.49	49.22	RT	6	
2047+13.18	30.39	RT	12	
2047+17.46	47.82	RT	8	
2047+21.77	44.99	LT	12	
2047+24.60	46.58	RT	12	
2047+39.39	50.02	RT	14	
2047+45.66	43.61	RT	10	
2047+45.94	45.28	RT	12	
2047+48.86	41.83	RT	10	
2047+55.28	41.65	LT	7	
2047+55.44	46.89	RT	10	
2047+62.57	47.97	RT	7	
2047+69.22	44.96	RT	14	
2047+95.75	38.05	LT		28
2047+96.17	49.07	RT	14	
2047+96.40	47.81	RT	6	
2047+99.83	38.05	LT		20
2048+01.33	45.92	RT	10	
2048+01.70	38.07	LT	14	
2048+03.16	37.90	LT	10	
2048+04.18	57.34	LT	6	
2048+12.23	38.72	LT	8	
2048+12.90	26.21	RT		18
2048+14.87	26.37	RT	8	
2048+17.70	32.56	RT		18
2048+18.45	47.82	RT	10	
2048+25.58	48.05	RT	6	
2048+27.39	33.69	LT	6	
2048+28.25	45.51	LT	15	
2048+28.56	33.76	LT	6	
2048+28.83	35.27	LT	6	
2048+30.06	33.79	LT	6	
2048+30.16	46.51	RT	7	
2048+37.81	36.93	LT	12	
2048+38.00	36.15	LT	12	
2048+38.47	49.20	RT	10	
2048+56.70	47.64	RT	8	
2048+62.83	45.96	LT	6	
2048+64.95	35.70	LT	12	
2048+66.59	41.65	LT	12	
2048+71.72	48.04	RT	8	

CONTINUED FROM PREVIOUS

2048+77.75	44.37	LT		22
2048+81.69	51.35	RT	10	
2048+86.25	44.14	RT	6	
2048+86.44	45.42	LT	12	
2048+91.15	49.08	RT	10	
2048+98.31	43.67	LT	14	
2049+00.05	43.52	LT	10	
2049+01.04	30.94	LT		16
2049+01.94	48.14	RT	10	
2049+02.12	49.37	RT	9	
2049+02.84	34.15	RT	9	
2049+02.89	33.99	RT	10	
2049+04.73	59.89	RT		26
2049+08.26	42.62	LT	12	
2049+08.59	36.54	LT	6	
2049+11.43	37.76	LT	8	
2049+43.38	50.54	LT	10	
2049+51.27	48.60	LT		18
2049+65.10	28.69	RT	7	
2049+65.62	42.57	RT	10	
2049+69.24	37.34	RT	10	
2049+69.32	41.45	LT	8	
2049+73.17	42.04	LT	12	
2049+74.65	33.26	RT	6	
2049+76.10	36.01	RT		26
2049+76.18	44.21	LT		16
2049+77.12	43.23	RT	8	
2049+78.51	36.70	RT	14	
2049+82.05	48.73	LT	12	
2049+86.55	31.96	RT	6	
2050+12.21	48.05	LT	12	
2050+15.24	46.04	LT		18
2050+51.37	51.28	LT	6	
2050+61.51	50.45	LT	15	
2050+70.90	35.75	RT		16
2050+71.35	38.13	RT	12	
2050+82.27	51.20	LT		16
2051+12.91	38.99	RT		20
2051+14.51	38.40	RT	6	
2051+17.53	37.26	RT	10	
2051+21.33	48.29	LT		16
2051+38.23	48.56	LT		16
2051+59.51	52.77	LT	8	
2051+68.32	51.66	LT	12	
2051+79.42	49.65	LT	8	
2051+88.65	48.52	LT	8	
2051+96.54	45.47	LT	10	
2052+04.13	45.26	LT		24
2052+08.91	46.57	LT		18
TOTAL			916	386

EROSION CONTROL SCHEDULE											
LOCATION		RIGHT OR LEFT	PERIMETER EROSION BARRIER FOOT	EROSION CONTROL BLANKET SQ YD	INLET AND PIPE PROTECTION EACH	TEMPORARY EROSION CONTROL SEEDING POUND	POTASSIUM FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	NITROGEN FERTILIZER NUTRIENT POUND	MULCH, METHOD 2 ACRE	SEEDING CLASS 2 ACRE
STA 2036+00	TO STA 2045+50	LT	107.4		1	0.0	0.0	0.0	0.0	0.00	0.00
STA 2036+00	TO STA 2045+50	RT	0.0			0.0	0.0	0.0	0.0	0.00	0.00
STA 2045+50	TO STA 2046+00	LT	50.0			9.0	2.7	2.7	2.7	0.03	0.03
STA 2045+50	TO STA 2046+00	RT	47.9			5.5	1.7	1.7	1.7	0.02	0.02
STA 2046+00	TO STA 2046+50	LT	50.0			17.9	5.4	5.4	5.4	0.05	0.05
STA 2046+00	TO STA 2046+50	RT	50.1			11.6	3.5	3.5	3.5	0.04	0.04
STA 2046+50	TO STA 2047+00	LT	50.0			18.9	5.7	5.7	5.7	0.06	0.06
STA 2046+50	TO STA 2047+00	RT	50.0	181.7		12.4	3.7	3.7	3.7	0.04	0.04
STA 2047+00	TO STA 2047+50	LT	50.0			17.7	5.3	5.3	5.3	0.05	0.05
STA 2047+00	TO STA 2047+50	RT	50.0	184.7		13.0	3.9	3.9	3.9	0.04	0.04
STA 2047+50	TO STA 2048+00	LT	50.0	214.2		15.0	4.5	4.5	4.5	0.05	0.05
STA 2047+50	TO STA 2048+00	RT	50.0	187.5		13.7	4.1	4.1	4.1	0.04	0.04
STA 2048+00	TO STA 2048+50	LT	50.0	190.3		14.5	4.3	4.3	4.3	0.04	0.04
STA 2048+00	TO STA 2048+50	RT	50.0	192.2		13.7	4.1	4.1	4.1	0.04	0.04
STA 2048+50	TO STA 2048+80.01	LT	65.8	112.5		8.4	2.5	2.5	2.5	0.03	0.03
STA 2048+50	TO STA 2048+80.01	RT	63.5	113.6		7.9	2.4	2.4	2.4	0.02	0.02
STA 2049+87.01	TO STA 2050+00	LT	58.3	65.4		3.9	1.2	1.2	1.2	0.01	0.01
STA 2049+87.01	TO STA 2050+00	RT	45.6	44.8		3.3	1.0	1.0	1.0	0.01	0.01
STA 2050+00	TO STA 2050+50	LT	97.1	232.5	1	13.9	4.2	4.2	4.2	0.04	0.04
STA 2050+00	TO STA 2050+50	RT	50.3	148.2	1	12.1	3.6	3.6	3.6	0.04	0.04
STA 2050+50	TO STA 2051+00	LT	50.7	177.9		11.4	3.4	3.4	3.4	0.03	0.03
STA 2050+50	TO STA 2051+00	RT	50.1	138.7		10.7	3.2	3.2	3.2	0.03	0.03
STA 2051+00	TO STA 2051+50	LT	50.4	164.3		10.7	3.2	3.2	3.2	0.03	0.03
STA 2051+00	TO STA 2051+50	RT	50.3	158.8		10.2	3.0	3.0	3.0	0.03	0.03
STA 2051+50	TO STA 2052+00	LT	50.6	163.7		11.1	3.3	3.3	3.3	0.03	0.03
STA 2051+50	TO STA 2052+00	RT	50.2	159.2		10.9	3.3	3.3	3.3	0.03	0.03
STA 2052+00	TO STA 2052+50	LT	29.2	175.2		5.8	1.7	1.7	1.7	0.02	0.02
STA 2052+00	TO STA 2052+50	RT	29.3	168.5		5.9	1.8	1.8	1.8	0.02	0.02
TOTAL			1447	3174	2	300	90	90	90	0.88	0.88

STAGING SCHEDULE									
LOCATION	HOT-MIX ASPHALT		TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A		RELOCATE TEMPORARY CONCRETE BARRIER FOOT	STEEL RAILING (TEMPORARY) FOOT	TRAFFIC BARRIER, TERMINAL, TYPE II EACH	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) EACH	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE) EACH
	BASE COURSE WIDENING, 9" SQ YD	PAVEMENT REMOVAL SQ YD	CONCRETE BARRIER FOOT	CONCRETE BARRIER FOOT					
STAGE I	152	152			387.5	32	2	2	
STAGE II	114	114	437.5		300	387.5			2
TOTAL	266	266 *	437.5		687.5	387.5	32	2	2

\* NOT A TOTAL QUANTITY FOR THIS STRUCTURE. SEE RESURFACING SCHEDULE.

Rev. 12-22-08

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SCHEDULES OF QUANTITIES				F.A.P. RTE. 42	SECTION 139BR	COUNTY BOND	TOTAL SHEETS 59	SHEET NO. 9	
g:\pwwork\pwwid\ot\challandeske\dms5175	ypin@97a.dgn	DRAWN -	REVISED -									SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS	FED. AID PROJECT	CONTRACT NO. 76391
	PLOT SCALE = 50.00' / IN.	CHECKED -	REVISED -														
	PLOT DATE = 12/11/2008	DATE -	REVISED -														