

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE	
			100% STATE TOTAL QUANTITIES	X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	97	97
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20	20
20200500	EARTH EXCAVATION (WIDENING)	CU YD	35	35
20300100	CHANNEL EXCAVATION	CU YD	2107	2107
20400800	FURNISHED EXCAVATION	CU YD	3585	3585
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	196	196
25000200	SEEDING, CLASS 2	ACRE	1	1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90
25100115	MULCH, METHOD 2	ACRE	1	1
25100630	EROSION CONTROL BLANKET	SQ YD	3174	3174
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300
28000400	PERIMETER EROSION BARRIER	FOOT	1447	1447
28000500	INLET AND PIPE PROTECTION	EACH	3	3
28100105	STONE RIPRAP, CLASS A3	SQ YD	16	16
28100109	STONE RIPRAP, CLASS A5	SQ YD	1192	1192
28200200	FILTER FABRIC	SQ YD	1192	1192
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	266	266
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1
40600300	AGGREGATE (PRIME COAT)	TON	3	3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	436	436
40600990	TEMPORARY RAMP	SQ YD	66	66
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	866	866
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	162	162
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	11	11
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	276	276
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35
44000100	PAVEMENT REMOVAL	SQ YD	673	673
44004250	PAVED SHOULDER REMOVAL	SQ YD	66	66
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	572	572
48203100	HOT-MIX ASPHALT SHOULDERS	TON	160	160
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50105220	PIPE CULVERT REMOVAL	FOOT	96	96
50200100	STRUCTURE EXCAVATION	CU YD	245	245

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE	
			100% STATE TOTAL QUANTITIES	X071-2A
50300225	CONCRETE STRUCTURES	CU YD	39	39
50300255	CONCRETE SUPERSTRUCTURE	CU YD	143	143
50300260	BRIDGE DECK GROOVING	SQ YD	372	372
50300300	PROTECTIVE COAT	SQ YD	466	466
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	1782	1782
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	35380	35380
50800515	BAR SPLICERS	EACH	395	395
50901125	STEEL RAILING (TEMPORARY)	FOOT	32	32
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	749	749
51202305	DRIVING PILES	FOOT	749	749
51203200	TEST PILE METAL SHELLS	EACH	2	2
51500100	NAME PLATES	EACH	1	1
52100520	ANCHOR BOLTS, 1"	EACH	24	24
54213447	END SECTIONS 12"	EACH	2	2
54213450	END SECTIONS 15"	EACH	2	2
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	120	120
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	83	83
60100945	PIPE DRAINS 12"	FOOT	64	64
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	158	158
60900515	CONCRETE THRUST BLOCKS	EACH	2	2
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2	2
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	950	950
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100110	TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2	2
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	1470	1470
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	20	20
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	7	7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1

\*Specialty Items

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\challandeske\dms51755\pln047.dgn	DRAWN -	REVISED -	REVISED -		42	139BR	BOND	59	3				
PLOT SCALE = 50.00' / 1"	CHECKED -	REVISED -	REVISED -		CONTRACT NO. 76391								
PLOT DATE = 10/22/2008	DATE -	REVISED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT