

GENERAL NOTES

1. FLAGMEN SHALL BE PRESENT DURING ALL CLOSURE HOURS, INCLUDING LUNCH HOUR, AND NO ADDITIONAL COMPENSATION SHALL BE APPLIED.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMEREN CIPS AERIAL
 - FRONTIER COMMUNICATIONS COMPANY AERIAL, BURIED
 - JERSEY COUNTY RURAL WATER COMPANY BURIED

(MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY *. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
4. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
5. ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND APPROPRIATE LIGHTS.
6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT EACH END OF THE PROJECT PLUS THE INTERSECTING SIDE ROADS, AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE (48X48).
7. "ALL AREAS DISTURBED FOR ANY REASON SHALL BE PERMANENTLY SEEDDED AS DIRECTED BY THE ENGINEER. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDDED AT THE CONTRACTORS EXPENSE."
8. THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING AND TOPO SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS MADE BY DESIGN PERSONNEL. BOTH SHALL BE ASSUMED TO BE APPROXIMATE
9. 3' REMOVAL AT SIDE ROAD STATION 189+80.00 (RIGHT)WILL BE PAID FOR AS "PAVED SHOULDER REMOVAL". NO ADDITIONAL COMPENSATION SHALL BE PAID. SAW CUTS SHALL ALSO BE CONSIDERED IN THE COST OF "PAVED SHOULDER REMOVAL".
10. REMOVAL OF EXISTING ENTRANCE MATERIAL REQUIRED TO PLACE HMA SHOULDER 10" WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF "PAVED SHOULDER REMOVAL".
11. PER ARTICLE 481.07 PRIOR TO PLACING THE AGGREGATE WEDGE SHOULDER TYPE B, THE CONTRACTOR SHALL CUT THE WEEDS AND GRASS ON THE AREA TO BE COVERED. COST IS INCLUDED IN AGGREGATE WEDGE SHOULDER, TYPE B AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

HIGHWAY STANDARDS

- 000001-05
- 482001-02
- 482006-03
- 642001-01
- 701306-02
- 701311-03
- 701326-03
- 701901-01

INDEX OF SHEETS

1. COVER SHEET
2. GENERAL NOTES, STANDARDS, COMMITMENTS, AND INDEX OF SHEETS
3. SUMMARY OF QUANTITIES
4. - 5. TYPICAL SECTIONS
6. ROADWAY LAYOUT
7. SCHEDULES
8. PLAN SHEET
9. DETAILS

COMMITMENTS

NO COMMITMENTS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, COMMITMENTS, INDEX OF SHEETS & LIST OF STANDARDS	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			747	(58,59)	JERSEY	9	2	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CONTRACT NO. 76C30					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	