

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	URBAN CONSTRUCTION TYPE CODE Y031-1/F 100 % STATE	
		UNIT	TOTAL QUANTITIES
44003800	MEDIAN SURFACE REMOVAL	SQ FT	231
60618300	CONCRETE MEDIAN SURFACE , 4 INCH	SQ FT	231
67100100	MOBILIZATION	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
80300100	LOCATING UNDERGROUND CABLE	FOOT	10
80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	36
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	115
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	184
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	13
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	8
81021550	CONDUIT, AUGURED, 2" DIA., PVC	FOOT	59
81021560	CONDUIT, AUGURED, 2 1/2" DIA., PVC	FOOT	169
81400100	HANDHOLE	EACH	7
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	356
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5/C	FOOT	1295
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7/C	FOOT	279
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	387
87301855	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 8 2C	FOOT	22
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87900100	DRILL EXISTING FOUNDATION	EACH	4
88500100	INDUCTIVE LOOP DETECTOR	EACH	3
88600100	DETECTOR LOOP, TYPE I	FOOT	305
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	2
89501100	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER	EACH	1
89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	2
89502380	REMOVE EXISTING HANDHOLE	EACH	3
89502385	RELOCATE EXISTING CONCRETE FOUNDATION	EACH	1
X0301576	COAXIAL CABLE IN CONDUIT	FOOT	73
X0324523	REMOVE FOUNDATION FOR BASE MOUNTED CONTROLLER	EACH	1