

SUMMARY OF QUANTITIES

| CODED PAY ITEM NO. | ITEM | UNIT | TOTAL QUANTITY |
|--------------------|--|-------|----------------|
| 20100110 | Tree Removal (6 to 15 units diameter) | unit | 30 |
| 20100210 | Tree Removal (over 15 units diameter) | unit | 39 |
| 20200100 | Earth Excavation | cu yd | 7290 |
| 20800150 | Trench Backfill | cu yd | 1261 |
| * 25000900 | Seeding, Class 1 (Special) | acre | 2.61 |
| * 25200700 | Sodding, Special | sq yd | 228 |
| 28000500 | Inlet and Pipe Protection | each | 78 |
| 28100105 | Stone RIP RAP, Class A3 | sq yd | 12 |
| * 28100107 | Stone RIP RAP, Class A4 | sq yd | 67 |
| 31100910 | Sub-base Granular Material, Type A 12" | sq yd | 13,558 |
| 35101600 | Aggregate Base Course, Type B 4" | sq yd | 5158 |
| 35102000 | Aggregate Base Course, Type B 8" | sq yd | 601 |
| 35102400 | Aggregate Base Course, Type B 12" | sq yd | 199 |
| 35501308 | Hot-Mix Asphalt Base Course, 6" | sq yd | 11,026 |
| 40201000 | Aggregate for Temporary Access | ton | 400 |
| 40600100 | Bituminous Materials (Prime Coat) | gal | 3935 |
| 40600625 | Leveling Binder (Machine Method), N50 | ton | 391 |
| 40600982 | Hot-Mix Asphalt Surface Removal - Butt Joint | sq yd | 547 |
| 40603080 | Hot-Mix Asphalt Binder Course, IL-19.0, N50 | ton | 1419 |
| 40603335 | Hot-Mix Asphalt Surface Course, Mix "D", N50 | ton | 2127 |
| 42300200 | Portland Cement Concrete Driveway Pavement, 6 inch | sq yd | 454 |
| 42400200 | Portland Cement Concrete Sidewalk 5 inch | sq ft | 42,387 |
| 42400800 | Detectable Warnings | sq ft | 121 |
| 44000100 | Pavement Removal | sq yd | 2848 |
| 44000200 | Driveway Pavement Removal | sq yd | 1142 |
| 44000500 | Combination Curb and Gutter Removal | foot | 215 |
| * 44300900 | Strip Reflective Crack Control Treatment, System A | foot | 7940 |
| 48100300 | Aggregate Shoulder, Type A 4" | sq yd | 44 |
| 50100300 | Removal of Existing Structures No. 1 | each | 1 |
| * 50105220 | Pipe Culvert Removal | foot | 1226 |
| 54001000 | Box Culvert End Sections | each | 2 |
| 54010606 | Precast Concrete Box Culvert 6'x 6' | foot | 78 |
| 54213663 | Precast Reinforced Concrete Flared End Sections 18" | each | 1 |
| 54214737 | Precast Reinforced Concrete Flared End Sections- Elliptical, Equivalent Round-Size 42" | each | 1 |
| 54216180 | Reinforced Concrete Pipe Tee, 12" Pipe with 12" Riser | each | 3 |
| 54216185 | Reinforced Concrete Pipe Tee, 15" Pipe with 12" Riser | each | 1 |
| 54216190 | Reinforced Concrete Pipe Tee, 18" Pipe with 12" Riser | each | 5 |
| 54216195 | Reinforced Concrete Pipe Tee, 21" Pipe with 12" Riser | each | 2 |
| 550A0050 | Storm Sewers, Class A, Type 1 12" | foot | 2715 |
| 550A0070 | Storm Sewers, Class A, Type 1 15" | foot | 359 |
| 550A0090 | Storm Sewers, Class A, Type 1 18" | foot | 1198 |
| 550A0110 | Storm Sewers, Class A, Type 1 21" | foot | 254 |
| 550A0120 | Storm Sewers, Class A, Type 1 24" | foot | 25 |
| 550A0140 | Storm Sewers, Class A, Type 1 30" | foot | 42 |
| 550A0340 | Storm Sewers, Class A, Type 2 12" | foot | 327 |
| 550A0380 | Storm Sewers, Class A, Type 2 18" | foot | 624 |
| 550A0400 | Storm Sewers, Class A, Type 2 21" | foot | 195 |
| 55034700 | Storm Sewers, Type 1, Reinforced Concrete Elliptical Pipe, Span 53, Rise 34 | foot | 67 |
| 60218400 | Manholes Type A, 4'-Diameter, Type 1 Frame, Closed Lid | each | 18 |
| 60219300 | Manholes Type A, 4'-Diameter, Type 11 Frame and Grate | each | 3 |
| 60221000 | Manholes Type A, 5'-Diameter, Type 1 Frame, Open Lid | each | 1 |
| 60221100 | Manholes Type A, 5'-Diameter, Type 1 Frame, Closed Lid | each | 1 |
| 60222000 | Manholes Type A, 5'-Diameter, Type 11 Frame and Grate | each | 2 |
| 60223700 | Manholes Type A, 6'-Diameter, Type 1 Frame, Open Lid | each | 1 |
| 60224445 | Manholes Type A, 7'-Diameter, Type 1 Frame, Open Lid | each | 1 |
| 60234200 | Inlets Type A, Type 1 Frame, Open Lid | each | 2 |
| 60235300 | Inlets Type A, Type 1 Frame, Closed Lid | each | 2 |
| 60236800 | Inlets Type A, Type 11 Frame and Grate | each | 19 |
| 60237490 | Inlets Type A, Type 37M Grate | each | 27 |

| CODED PAY ITEM NO. | ITEM | UNIT | TOTAL QUANTITY |
|-----------------------|---|----------|----------------|
| 60240210 | Inlets Type B, Type 1 Frame, Open Lid | each | 3 |
| 60240215 | Inlets Type B, Type 1 Frame, Closed Lid | each | 7 |
| 60240310 | Inlets Type B, Type 11 Frame and Grate | each | 18 |
| 60240330 | Inlets Type B, Type 37M Grate | each | 2 |
| 60255500 | Manholes to be Adjusted | each | 7 |
| 60257900 | Manholes to be Reconstructed | each | 2 |
| 60300105 | Frames and Grates to be Adjusted | each | 3 |
| 60500060 | Removing Inlets | each | 1 |
| 60603800 | Combination Concrete Curb and Gutter, Type B-6.12 | foot | 9536 |
| 63200310 | Guardrail Removal | foot | 134 |
| 67100100 | Mobilization | lump sum | 1 |
| * 70101700 | Traffic Control and Protection | lump sum | 1 |
| * 70300220 | Temporary Pavement Marking, Line 4" | foot | 1130 |
| 72000100 | Sign Panel - Type 1 | sq ft | 25.30 |
| 72800100 | Telescoping Steel Sign Support | foot | 223 |
| Δ 78000100 | Thermoplastic Pavement Marking - Letters and Symbols | sq ft | 1035.4 |
| Δ 78000400 | Thermoplastic Pavement Marking - Line 6" | foot | 13,501 |
| Δ 78000500 | Thermoplastic Pavement Marking - Line 8" | foot | 3642 |
| Δ 78000600 | Thermoplastic Pavement Marking - Line 12" | foot | 539 |
| Δ 78000650 | Thermoplastic Pavement Marking - Line 24" | foot | 139 |
| Δ 78001110 | Paint Pavement Marking - Line 4" | foot | 150 |
| * X0504200 | Concrete Headwall | each | 2 |
| * X0656300 | Pavement Removal and Replacement | sq yd | 291 |
| * X7240500 | Relocate Existing Signs | each | 9 |
| * XX000610 | Relocate Existing Mailbox | each | 30 |
| Δ * XX001877 | Sump Pump Line Connection | each | 4 |
| * XX003437 | Remove and Reinstall Existing Precast Reinforced Concrete Flared End Sections | each | 2 |
| * XX005843 | Incidental Bituminous Surfacing | sq yd | 601 |
| * XX007183 | Combination Concrete Curb and Gutter, Type M-3.12 | foot | 7 |
| * XX104100 | Connection to Existing Manhole | each | 2 |
| * XZ127900 | Retaining Wall Removal | foot | 61 |
| * XO322054 | Removal of Precast Flared End Section | each | 3 |
| * XX007493 | Connect to Box Culvert | each | 1 |

* See Special Provisions
 Δ Specialty Items



| REVISIONS | | | |
|-----------|---------|-------------------------------|--|
| DATE | BY | DESCRIPTION | |
| 2/11/08 | AJC/JWP | PER IDOT REVIEW | |
| 3/27/08 | JWP | PER IDOT REVIEW | |
| 4/1/08 | JWP | PER IDOT REVIEW | |
| 5/7/08 | JWP | BKE PATH REVISION FOR COMMENT | |
| 6/23/08 | JWP | ADD MOBILIZATION | |