

TREE REMOVAL SCHEDULE			
STATION	OFFSET	6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
63+78	31' R		21
68+57	31' R		18
92+02	34' R	15	
92+02	38' R	15	
	TOTAL	30	39

REMOVE EXISTING STRUCTURES SCHEDULE			
LOCATION	SIZE AND TYPE	LENGTH	STRUCTURE NO 1
		FOOT	EACH
STA 91+90 - 14 L TO 12 R	6x6' PCC CULVERT & HEADWALLS	25	1

EARTH EXCAVATION SCHEDULE	
LOCATION	EARTH EXCAVATION
	CU YD
STA 56+38 TO STA 104+68	7290
TOTAL	7290

SUMP SCHEDULE	
LOCATION	SUMP PUMP CONNECTION
	EACH
STA 56+99 - 29 L	1
STA 67+84 - 28 R	1
STA 75+07 - 33 R	1
STA 97+07 - 37 L	1
TOTAL	4

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6208	07-00093-00-RP	KANKAKEE	43	05
MGZA# M2-096		CONTRACT NO.: 87342		

TRENCH BACKFILL SCHEDULE		
LOCATION	TRENCH BACKFILL	DESCRIPTION
	CU YD	
STA 56+39 TO 56+66	9	CARDINAL
STA 56+39 TO 56+70 LT	8	DRIVE
STA 56+69 TO 56+99 RT	7	DRIVE
STA 57+24 TO 57+54 LT	6	DRIVE
STA 58+15 TO 58+46 RT	10	DRIVE
STA 58+82 TO 59+06 LT	8	DRIVE
STA 59+13 TO 59+45 RT	11	DRIVE
STA 59+17 TO 59+40 LT	7	DRIVE
STA 59+92 TO 60+00	16	CARDINAL/SIDEWALK
STA 60+15 TO 60+47 RT	16	DRIVE
STA 61+08 TO 61+30 LT	6	DRIVE
STA 61+17 TO 61+47 RT	10	DRIVE
STA 61+93 TO 62+00	5	SIDEWALK
STA 62+09 TO 62+40 RT	13	DRIVE
STA 62+58	14	CARDINAL/SIDEWALK
STA 63+20 TO 63+51 RT	9	DRIVE
STA 63+53 TO 63+60	2	CARDINAL
STA 63+75 TO 64+05 RT	8	DRIVE
STA 65+15 TO 65+44 RT	12	DRIVE
STA 65+69 TO 66+01 RT	17	DRIVE
STA 66+15	8	CARDINAL
STA 67+13 TO 67+42 RT	9	DRIVE
STA 70+26 TO 72+23 RT	61	CARDINAL
STA 72+23 TO 72+31	20	CARDINAL
STA 72+15 TO 72+30 LT	11	SIDEWALK
STA 72+23 TO 74+20 RT	84	CARDINAL
STA 74+20	15	CARDINAL
STA 74+20 TO 77+20 RT	133	CARDINAL
STA 77+20	15	CARDINAL/SIDEWALK
STA 77+20 TO 79+40 RT	82	CARDINAL
STA 79+40	23	CARDINAL/SIDEWALK
STA 78+40 TO 80+50 RT	20	CARDINAL
STA 80+50	9	CARDINAL/SIDEWALK
STA 82+27	4	CARDINAL
STA 82+27 TO 85+00 RT	29	CARDINAL
STA 85+00	7	CARDINAL/SIDEWALK
STA 85+00 TO 87+00 RT	22	CARDINAL
STA 87+00	6	CARDINAL
STA 87+00 TO 91+00 RT	163	CARDINAL
STA 91+00	18	CARDINAL/SIDEWALK
STA 91+00 TO 91+86 RT	63	CARDINAL
STA 91+88	203	CARDINAL/SIDEWALK
STA 94+30	5	CARDINAL
STA 98+50	14	CARDINAL/SIDEWALK
STA 100+97 LT	4	SIDEWALK
STA 100+95 TO 102+24 LT	22	SIGNATURE
STA 102+24	12	CARDINAL
STA 104+00	5	CARDINAL
TOTAL	1261	

REMOVALS SCHEDULE							
LOCATION	GUARDRAIL REMOVAL	PIPE CULVERT REMOVAL	RETAINING WALL REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	REMOVE INLET	SALVAGE PRC FLARED END SECTION	REMOVE PRC FLARED END SECTION
	FT	FT	FT	FT	EACH	EACH	EACH
STA 56+39 LT TO 56+66 RT		49				1	
STA 56+39 TO 56+81 - 25' LT		36					1
STA 56+65 TO 57+15 - 25' RT		50					
STA 57+29 TO 57+49 - 24' LT		20					
STA 57+69 TO 57+89 - 25' LT		20					
STA 58+19 TO 58+41 - 26' RT		22					
STA 58+82 TO 59+05 - 24' LT		23					
STA 59+16 TO 59+56 - 25' RT		40					
STA 59+19 TO 59+39 - 24' LT		20					
STA 59+92 TO 61+38 - 25' LT		146					
STA 60+19 TO 60+43 - 25' RT		24					
STA 61+20 RT			12				
STA 61+20 TO 61+45 - 25' RT		25					
STA 61+45 RT			14				
STA 62+11 RT			19				
STA 62+11 TO 62+35 - 25' RT		24					
STA 62+35 RT			16				
STA 62+52 - 36' LT							1
STA 62+58 - 26' LT						1	
STA 62+61 TO 62+82 - 25' RT		21					
STA 63+23 TO 63+45 - 25' RT		22					
STA 63+81 TO 64+03 - 24' RT		22					
STA 65+18 TO 65+40 - 25' RT		22					
STA 65+59 TO 65+94 - 25' RT		35					
STA 67+16 TO 67+37 - 26' RT		21					
STA 67+53 TO 67+73 - 26' RT		20					
STA 68+06 TO 68+27 - 26' RT		21					
STA 68+36 TO 68+76 LT				60			
STA 69+11 TO 69+50 LT				60			
STA 70+00 TO 70+66 - 26' RT		66					
STA 71+84 TO 72+06 - 26' RT		22					
STA 72+23 - 32' LT							1
STA 72+23 - 26' RT					1		
STA 72+50 TO 72+74 - 26' RT		24					
STA 73+84 TO 74+36 - 26' RT		52					
STA 74+82 TO 75+04 - 26' RT		22					
STA 75+34 TO 75+56 - 26' RT		22					
STA 76+89 TO 77+10 - 27' RT		21					
STA 77+79 TO 78+58 - 27' RT		79					
STA 81+25 TO 81+64 LT				60			
STA 81+97 TO 82+12 LT				35			
STA 89+46 TO 89+70 - 23' LT		24					
STA 91+05 TO 91+26 - 25' LT		21					
STA 91+59 TO 92+25 - 15' LT	67						
STA 91+59 TO 92+25 - 15' RT	67						
STA 94+45 TO 94+68 - 23' LT		23					
STA 100+93 TO 102+28 - 23' LT		135					
STA 104+39 TO 104+63 - 25' RT		24					
STA 104+53 LT		8					
TOTAL	134	1226	61	215	1	2	3

PAVEMENT REMOVAL SCHEDULE					
LOCATION	PAVEMENT REMOVAL	PAVEMENT REMOVAL AND REPLACEMENT	DRIVEWAY PAVEMENT REMOVAL	HOT MIX ASPHALT SURFACE REMOVAL BUTT JOINT	DESCRIPTION
	SQ YD	SQ YD	SQ YD	SQ FT	
STA 56+36 TO 56+76				111	CARDINAL
STA 56+50 - LT			47		
STA 56+52		17			STORM
STA 56+83 - RT			54		
STA 57+40 - LT			37		
STA 57+80 - LT			46		
STA 58+31 - RT			53		
STA 58+95 - LT			14		
STA 59+30 - RT			54		
STA 59+30 - LT			59		
STA 59+95		15			STORM
STA 60+00 TO 64+60	1105				CARDINAL
STA 60+15 - LT			47		
STA 60+31 - RT			58		
STA 61+20 - LT			46		
STA 61+30 - RT			51		
STA 63+37 - RT			49		
STA 63+91 - RT			55		
STA 65+30 - RT			53		
STA 65+85 - RT			8		
STA 66+15		14			STORM
STA 67+29 - RT			54		
STA 68+16 - RT			55		
STA 68+30 TO 68+77 - LT	40				NORTHFIELD
STA 68+92 - LT				54	NORTHFIELD
STA 68+92 - RT				31	DALE
STA 69+09 TO 69+85 - LT	52				NORTHFIELD
STA 70+50 - RT			14		
STA 71+25 TO 73+90	700				CARDINAL
STA 71+95 - RT			46		
STA 72+63 - RT			58		
STA 74+20		14			STORM
STA 74+97 - RT			55		
STA 77+00 - RT			48		
STA 77+20		14			STORM
STA 77+95 - RT			57		
STA 78+45 - RT			24		
STA 79+40		14			STORM
STA 80+50		14			STORM
STA 81+20 TO 81+65 - LT	42				LEMNA
STA 81+80 - LT				49	LEMNA
STA 81+80 - RT				99	YORKTOWN
STA 81+95 TO 82+35 - LT	35				LEMNA
STA 82+30		18			STORM
STA 85+00		13			STORM
STA 85+25 TO 86+50	800				CARDINAL
STA 91+00		13			STORM
STA 91+74 TO 92+04	70				CARDINAL
STA 94+30		14			STORM
STA 98+50		13			STORM
STA 101+03 TO 102+16		87			STORM
STA 101+06 TO 101+21 - LT	2				CARDINAL
STA 101+60 - LT				104	SIGNATURE
STA 102+01 TO 101+13 - LT	2				CARDINAL
STA 102+22		18			STORM
STA 104+00		13			STORM
STA 104+68 TO 105+08				99	CARDINAL
TOTAL	2848	291	1142	547	

PAVEMENT MARKINGS SCHEDULE								
LOCATION	TEMPORARY PAVEMENT MARKING LINE 4"	PAINT PAVEMENT MARKING LINE 4"	THERMOPLASTIC PAVEMENT MARKING				DESCRIPTION	
			LETTERS & SYMBOLS	LINE 6"	LINE 8"	LINE 12"		LINE 24"
	FT	FT	SQ FT	FT	FT	FT	FT	
STA 56+36 TO 104+68	1130							SKIP DASH YELLOW
STA 56+36 TO 61+57					34			SKIP DASH WHITE
STA 56+36 TO 61+57				1329		50		SOLID LINE YELLOW
STA 56+36 TO 61+57					1408			SOLID LINE WHITE
STA 56+36 TO 61+57			190.1					WHITE
STA 61+57 TO 65+75				220				SKIP DASH YELLOW
STA 61+57 TO 65+75				836				SOLID LINE YELLOW
STA 61+57 TO 65+75			62.4					WHITE
STA 61+57 TO 65+75					836			SOLID LINE WHITE
STA 65+75 TO 68+55					34			SKIP DASH WHITE
STA 65+75 TO 68+55				848		50		SOLID LINE YELLOW
STA 65+75 TO 68+55					694			SOLID LINE WHITE
STA 65+75 TO 68+55			106.9					WHITE
STA 65+75 TO 68+55						30		STOP BAR WHITE
STA 68+55 TO 69+31				223				SOLID LINE WHITE
STA 68+55 TO 69+31						43		STOP BAR WHITE
STA 68+92 - RT		20						SKIP DASH YELLOW
STA 68+92 - RT		130						SOLID LINE WHITE
STA 69+31 TO 72+11					34			SKIP DASH WHITE
STA 69+31 TO 72+11				848		67		SOLID LINE YELLOW
STA 69+31 TO 72+11					125			SOLID LINE WHITE
STA 69+31 TO 72+11			83.2					WHITE
STA 69+31 TO 72+11						30		STOP BAR WHITE
STA 72+11 TO 78+63				340				SKIP DASH YELLOW
STA 72+11 TO 78+63				1304				SOLID LINE YELLOW
STA 72+11 TO 78+63			124.8					WHITE
STA 78+63 TO 81+43					34			SKIP DASH WHITE
STA 78+63 TO 81+43				848		67		SOLID LINE YELLOW
STA 78+63 TO 81+43					125			SOLID LINE WHITE
STA 78+63 TO 81+43			83.2					WHITE
STA 81+43 TO 82+17				370				SOLID LINE WHITE
STA 81+43 TO 82+17					34			SKIP DASH WHITE
STA 82+17 TO 84+97					848		67	SOLID LINE YELLOW
STA 82+17 TO 84+97						125		SOLID LINE WHITE
STA 82+17 TO 84+97			83.2					WHITE
STA 84+97 TO 98+37				700				SKIP DASH YELLOW
STA 84+97 TO 98+37				2680				SOLID LINE YELLOW
STA 84+97 TO 98+37			218.4					WHITE
STA 98+37 TO 101+17					34			SKIP DASH WHITE
STA 98+37 TO 101+17				848		67		SOLID LINE YELLOW
STA 98+37 TO 101+17					125			SOLID LINE WHITE
STA 98+37 TO 101+17			83.2					WHITE
STA 101+17 TO 102+07				198				SOLID LINE WHITE
STA 102+07 TO 104+68				1061		171		SOLID LINE YELLOW
TOTAL	1130	150	1035.4	13501	3642	539	139	

