F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6208	07-00093-00-RP	KANKAKEE	43	08
MG2A# M2-096		CONTRACT NO.: 87342		

STORM SEWER PIPE SCHEDULE

LOCATION	Structure ID	RCP STORM SEWER CLASS A TYPE 1							RCP STORM SEWER CLASS A TYPE 2		
		12"	15"	18"	21"	24"	30"	42" EDE	12"	18"	21"
		FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET
STA: 56+54 - 33 R TO STA: 56+67 - 27 R	1C1 - 1C	13									
STA: 56+67 - 27 R TO STA: 56+39 - 25 L	1C - 1	58									
STA: 56+94 - 29 L TO STA: 56+39 - 25 L	1A - 1	53									
STA: 57+22 - 27 R TO STA: 56+67 - 27 R	1D - 1C	54									
STA: 57+24 - 33 R TO STA: 57+22 - 27 R	1D1 - 1D	5									
STA: 57+59 - 29 L TO STA: 56+94 - 29 L	1B - 1A	64									
STA: 58+04 - 33 R TO STA: 58+08 - 27 R	2K1 - 2K	6									
STA: 58+08 - 27 R TO STA: 59+01 - 27 R	2K - 2J								91		
STA: 58+68 - 36 L TO STA: 59+12 - 36 L	2H5 - 2H4	44									
STA: 59+01 - 27 R TO STA: 60+00 - 27 R	2J - 2H	97									
STA: 59+01 - 33 R TO STA: 59+01 - 27 R	2J1 - 2J	5									
STA: 59+12 - 36 L TO STA: 59+89 - 36 L	2H4 - 2H3	75									
STA: 59+89 - 36 L TO STA: 59+92 - 22.7 L	2H3 - 2H2	17									
STA: 59+93 - 18 L TO STA: 60+00 - 22 R	2H2 - 2H1		39								
STA: 60+00 - 22 R TO STA: 60+00 - 27 R	2H1 - 2H		3								
STA: 60+00 - 27 R TO STA: 61+06 - 27 R	2H - 2G			105							
STA: 60+00 - 33 R TO STA: 60+00 - 27 R	2H6 - 2H	4									
STA: 60+97 - 36 L TO STA: 61+51 - 36 L	2C7 - 2C5	53									
STA: 61+06 - 27 R TO STA: 61+59 - 27 R	2G - 2F			55							
STA: 61+06 - 33 R TO STA: 61+06 - 27 R	2G1 - 2G	5									
STA: 61+51 - 36 L TO STA: 62+00 - 36 L	2C5 - 2C2		47								
STA: 61+51 - 46 L TO STA: 61+51 - 36 L	2C6 - 2C5	2									
STA: 61+58 - 33 R TO STA: 61+59 - 27 R	2F1 - 2F	7									
STA: 61+59 - 27 R TO STA: 62+00 - 27 R	2F - 2D				37						
STA: 61+93 - 18 L TO STA: 62+00 - 18 L	2C4 - 2C3	5									
STA: 61+93 - 22 R TO STA: 62+00 - 22 R	2D2 - 2D1	5									
STA: 62+00 - 18 L TO STA: 62+00 - 36 L	2C3 - 2C2	17									
STA: 62+00 - 22 R TO STA: 62+00 - 27 R	2D1 - 2D	3									
STA: 62+00 - 36 L TO STA: 62+52 - 36 L	2C2 - 2C		51								
STA: 62+00 - 27 R TO STA: 62+59 - 27 R	2D - 2A				57						
STA: 62+52 - 42 L TO STA: 62+52 - 36 L	2C1 - 2C					6					
STA: 62+52 - 36 L TO STA: 62+58 - 35 L	2C - 2B					4					
STA: 62+58 - 35 L TO STA: 62+59 - 27 R	2B - 2A							60			
STA: 62+59 - 27 R TO STA: 62+59 - 35 R	2A - 2							7			
STA: 62+66 - 44 L TO STA: 62+58 - 35 L	2B1 - 2B		6								
STA: 63+53 - 18 L TO STA: 63+53 - 22 R	2L3 - 2L1	38									
STA: 63+53 - 22 R TO STA: 63+53 - 27 R	2L1 - 2L	4									
STA: 63+53 - 27 R TO STA: 62+59 - 27 R	2L - 2A				93						
STA: 63+55 - 33 R TO STA: 63+53 - 27 R	2L5 - 2L	5									
STA: 63+60 - 18 L TO STA: 63+53 - 18 L	2L4 - 2L3	5									
STA: 63+60 - 22 R TO STA: 63+53 - 22 R	2L2 - 2L1	6									
STA: 64+07 - 27 R TO STA: 63+53 - 27 R	2M - 2L			53							
STA: 64+07 - 33 R TO STA: 64+07 - 27 R	2M1 - 2M	5									
STA: 65+58 - 27 R TO STA: 64+07 - 27 R	2M2 - 2M			149							
STA: 65+58 - 33 R TO STA: 65+58 - 27 R	2M3 - 2M2	5									
STA: 66+15 - 18 L TO STA: 66+15 - 22 R	2N2 - 2N1	38									
STA: 66+15 - 22 R TO STA: 66+15 - 27 R	2N1 - 2N	4									
STA: 66+15 - 27 R TO STA: 65+58 - 27 R	2N - 2M2			56							
STA: 66+15 - 33 R TO STA: 66+15 - 27 R	2N3 - 2N	5									
STA: 67+51 - 27 R TO STA: 66+15 - 27 R	2N4 - 2N	135									
STA: 67+51 - 34 R TO STA: 67+51 - 27 R	2N5 - 2N4	6									
STA: 67+84 - 28 R TO STA: 67+51 - 27 R	2N6 - 2N4	32									
STA: 70+25 - 33 R TO STA: 70+28 - 15 R	3B3 - 3B2	17									
STA: 70+28 - 15 R TO STA: 71+30 - 15 R	3B2 - 3B								101		
STA: 71+30 - 15 R TO STA: 72+23 - 15 R	3B - 3A								91		
STA: 71+30 - 33 R TO STA: 71+30 - 15 R	3B1 - 3B	17									
STA: 72+11 - 42 L TO STA: 72+23 - 22 L	3A6 - 3A4	22									
STA: 72+23 - 15 R TO STA: 72+23 - 22 R	3A - 3A1						5				
STA: 72+23 - 18 L TO STA: 72+23 - 15 R	3A3 - 3A						31				
STA: 72+23 - 22 L TO STA: 72+23 - 18 L	3A4 - 3A3						3				
STA: 72+23 - 22 R TO STA: 72+23 - 27 R	3A1 - 3						3				
STA: 72+23 - 37 L TO STA: 72+23 - 22 L	3A7 - 3A4	14									
STA: 72+31 - 18 L TO STA: 72+23 - 18 L	3A5 - 3A3	6									
STA: 72+31 - 22 R TO STA: 72+23 - 22 R	3A2 - 3A1	6									
STA: 73+24 - 15 R TO STA: 72+23 - 15 R	3C - 3A										100
STA: 73+24 - 33 R TO STA: 73+24 - 15 R	3C1 - 3C	17									
STA: 74+20 - 15 R TO STA: 73+24 - 15 R	3D - 3C										95
STA: 74+20 - 18 L TO STA: 74+20 - 15 R	3D1 - 3D	32									
STA: 74+20 - 22 R TO STA: 74+20 - 15 R	3D2 - 3D								6		
STA: 74+24 - 34 R TO STA: 74+20 - 22 R	3D3 - 3D2	12									
STA: 75+07 - 15 R TO STA: 74+20 - 15 R	3D4 - 3D									86	
STA: 75+07 - 33 R TO STA: 75+07 - 15 R	3D5 - 3D4	17									
STA: 76+26 - 15 R TO STA: 75+07 - 15 R	3D6 - 3D4									118	
STA: 76+26 - 33 R TO STA: 76+26 - 15 R	3D7 - 3D6	17									
STA: 77+20 - 15 R TO STA: 76+26 - 15 R	3E - 3D6									94	
STA: 77+20 - 18 L TO STA: 77+20 - 15 R	3E1 - 3E	32									
STA: 77+20 - 22 R TO STA: 77+20 - 15 R	3E3 - 3E								6		
STA: 77+20 - 36 L TO STA: 77+20 - 18 L	3E2 - 3E1	17									
STA: 79+40 - 15 R TO STA: 77+20 - 15 R	3E5 - 3E									218	
STA: 79+40 - 37 L TO STA: 79+40 - 15 R	3E6 - 3E5	51									
STA: 79+40 - 41 R TO STA: 79+40 - 15 R	3E7 - 3E5	25									
STA: 80+50 - 15 R TO STA: 79+40 - 15 R	3F - 3E5		109								
STA: 80+50 - 18 L TO STA: 80+50 - 15 R	3F1 - 3F	32									
STA: 80+50 - 22 R TO STA: 80+50 - 15 R	3F3 - 3F	6									
STA: 80+55 - 37 L TO STA: 80+50 - 18 L	3F2 - 3F1	19									

STORM SEWER PIPE SCHEDULE

LOCATION	Structure ID	RCP STORM SEWER CLASS A TYPE 1							RCP STORM SEWER CLASS A TYPE 2		
		12"	15"	18"	21"	24"	30"	42" EDE	12"	18"	21"
		FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET
STA: 82+25 - 22 R TO STA: 82+33 - 15 R	4E2 - 4E	6									
STA: 82+27 - 18 L TO STA: 82+33 - 15 R	4E1 - 4E	32									
STA: 82+33 - 15 R TO STA: 85+00 - 15 R	4E - 4D	272									
STA: 85+00 - 15 R TO STA: 87+00 - 15 R	4D - 4C	198									
STA: 85+00 - 18 L TO STA: 85+00 - 15 R	4D1 - 4D	32									
STA: 85+00 - 22 R TO STA: 85+00 - 15 R	4D2 - 4D	6									
STA: 86+92 - 18 L TO STA: 87+00 - 18 L	4C2 - 4C1	7									
STA: 86+92 - 22 R TO STA: 87+00 - 22 R	4C5 - 4C4	7									
STA: 85+00 - 37 L TO STA: 85+00 - 18 L	4D3 - 4D1	19									
STA: 87+00 - 15 R TO STA: 91+00 - 15 R	4C - 4B			398							
STA: 87+00 - 18 L TO STA: 87+00 - 15 R	4C1 - 4C	32									
STA: 87+00 - 22 R TO STA: 87+00 - 15 R	4C4 - 4C	6									
STA: 90+78 - 39 L TO STA: 91+00 - 18 L	4B2 - 4B1	29									
STA: 91+00 - 15 R TO STA: 91+87 - 15 R	4B - 4A									86	
STA: 91+00 - 18 L TO STA: 91+00 - 15 R	4B1 - 4B								32		
STA: 91+00 - 22 R TO STA: 91+00 - 15 R	4B3 - 4B	6									
STA: 92+20 - 38 R TO STA: 91+99 - 47 R	4G - 4F									22	
STA: 94+30 - 18 L TO STA: 94+30 - 22 R	4H2 - 4H1		38								
STA: 94+30 - 22 R TO STA: 94+30 - 38 R	4H1 - 4H		14								
STA: 94+30 - 38 R TO STA: 92+20 - 38 R	4H - 4G			208							
STA: 94+37 - 18 L TO STA: 94+30 - 18 L	4H3 - 4H2	6									
STA: 97+07 - 37 L TO STA: 98+50 - 37 L	4K4 - 4K3	142									
STA: 98+50 - 18 L TO STA: 98+50 - 22 R	4K2 - 4K1	38									
STA: 98+50 - 22 R TO STA: 98+30 - 38 R	4K1 - 4K	24									
STA: 98+50 - 37 L TO STA: 98+50 - 18 L	4K3 - 4K2	17									
STA: 98+30 - 38 R TO STA: 94+30 - 38 R	4K - 4H	398									
STA: 100+95.5 - 21 L TO STA: 102+24 - 21 L	5B3 - 5B2	127									
STA: 100+99 - 38 L TO STA: 100+95.5 - 21 L	5B4 - 5B3	17									
STA: 102+19 - 22 R TO STA: 102+19 - 31 R	5B1 - 5B		11								
STA: 102+19 - 31 R TO STA: 104+00 - 31 R	5B - 5A			174							
STA: 102+24 - 21 L TO STA: 102+19 - 22 R	5B2 - 5B1		41								
STA: 104+00 - 18 L TO STA: 104+00 - 22 R	5A2 - 5A1	38									
STA: 104+00 - 22 R TO STA: 104+00 - 31 R	5A1 - 5A	11									
STA: 104+00 - 31 R TO STA: 104+68 - 33 R	5A - 5				67						
STA: 104+45 - 39 L TO STA: 104+52 - 39 L	6A1 - 6A	6									
STA: 104+52 - 39 L TO STA: 104+68 - 38 L	6A - 6					15					
TOTAL		2715	359	1198	254	25	42	67	327	624	195

CULVERT SCHEDULE

LOCATION	PRECAST CONCRETE BOX CULVERT (ASTM C850) 6'x 6'	PRECAST CONCRETE BOX CULVERT END SECTIONS	CONCRETE HEADWALL
	FT	EACH	EACH
STA: 91+81 - 48 L TO 91+93 - 41 R	78	2	2

M. GINGERICH, GEREAUX & ASSOCIATES
240 N. Industrial Drive
Bradley, Illinois 60915
815-939-4921
FAX : 815-939-9810

REVISIONS

DATE	BY	DESCRIPTION
2/11/08	AJC/JWP	PER IDOT REVIEW
3/27/08	JWP	PER IDOT REVIEW
4/1/08	JWP	PER REVIEWS
5/7/08	JWP	BIKE PATH REVISION PER COMMENT

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES SHEET
CARDINAL DRIVE

SCALE:
DRAWN BY: MJO/AJC
DATE: 1/4/08
CHECKED BY: JWP