

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	5
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. RS-HPP-1805(001)				
CONTRACT NO. 91368				

CODE NO.	ITEM	SAFETY CODE		2A		1E		1F	
		CONSTRUCTION CODE		J000	J000	Y030	Y030	Y031	Y031
		UNIT	TOTAL QUANTITY	ROADWAY CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	ROADWAY SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY	ROADWAY LIGHTING CHAMPAIGN SECTION 100% CITY	ROADWAY LIGHTING SAVOY SECTION 100% VILLAGE	TRAFFIC SIGNALS CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	TRAFFIC SIGNALS SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY
30201250	PROCESSING MODIFIED SOIL 24"	SQ YD	38,593	19,369	19,224				
30201500	LIME	TON	2,050	1,106	944				
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1,726	980	746				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	18,506	10,121	8,385				
* 31200100	STABILIZED SUB-BASE 4"	SQ YD	61,741	34,673	27,068				
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	7,743		7,743				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	205	205					
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1,123		1,123				
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	2,099		2,099				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	679	104	575				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	420		420				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,581	5,061	5,520				
40600300	AGGREGATE (PRIME COAT)	TON	16		16				
40600400	MIXTURE FOR CRACKS JOINTS AND FLANGEWAYS	TON	2		2				
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	81		81				
40600895	CONSTRUCTING TEST STRIP	EACH	11	4	7				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	385		385				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	99		99				
40600990	TEMPORARY RAMP	SQ YD	354		354				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	634	445	189				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1,337		1,337				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	432	300	132				
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	856		856				
* 42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	57,877	30,564	27,313				
42001300	PROTECTIVE COAT	SQ YD	63,731	32,857	30,874				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	183		183				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	677	195	482				
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	35,590	8,735	26,855				
42400800	DETECTABLE WARNINGS	SQ FT	389	187	202				
44000100	PAVEMENT REMOVAL	SQ YD	490	490					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	712		712				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,122	24	2,098				
44000600	SIDEWALK REMOVAL	SQ FT	15,686	1,245	14,441				
* 44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	30,095	16,303	13,792				
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	123		123				

*SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.

SCALE : NONE