

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	6
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. RS-HPP-18051000				
CONTRACT NO. 91368				

CODE NO.	ITEM	SAFETY CODE		2A	2A	1E	1E	1F	1F
		CONSTRUCTION CODE		J000	J000	Y030	Y030	Y031	Y031
		UNIT	TOTAL QUANTITY	ROADWAY CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	ROADWAY SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY	ROADWAY LIGHTING CHAMPAIGN SECTION 100% CITY	ROADWAY LIGHTING SAVOY SECTION 100% VILLAGE	TRAFFIC SIGNALS CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	TRAFFIC SIGNALS SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,494		4,494				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	42		42				
48203017	HOT-MIX ASPHALT SHOULDERS, 5"	SQ YD	17,215	9,452	7,763				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	728	320	408				
* 50104400	CONCRETE HEADWALL REMOVAL	EACH	6		6				
* 50105210	REMOVE EXISTING CULVERTS	FOOT	904	480	424				
50200100	STRUCTURE EXCAVATION	CU YD	516	516					
50300220	CLASS MS CONCRETE	CU YD	13.6	13.6					
50300225	CONCRETE STRUCTURES	CU YD	78.2	78.2					
50800105	REINFORCEMENT BARS	POUND	7,130	7,130					
Δ* 50900805	PEDESTRIAN RAILING	FOOT	100	100					
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2					
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2					
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2					
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2	2					
54001005	BOX CULVERT END SECTION, CULVERT NO. 5	EACH	1	1					
54001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	2		2				
54001007	BOX CULVERT END SECTION, CULVERT NO. 7	EACH	2		2				
54001008	BOX CULVERT END SECTION, CULVERT NO. 8	EACH	1		1				
54010802	PRECAST CONCRETE BOX CULVERT 8'X2'	FOOT	90		90				
54010803	PRECAST CONCRETE BOX CULVERT 8'X3'	FOOT	24	24					
54011003	PRECAST CONCRETE BOX CULVERT 10'X3'	FOOT	168	168					
54011204	PRECAST CONCRETE BOX CULVERT 12'X4'	FOOT	120	120					
54020403	PRECAST CONCRETE BOX CULVERT 4'X3' (M273)	FOOT	270	270					
54020802	PRECAST CONCRETE BOX CULVERT 8'X2' (M273)	FOOT	114		114				
54020803	PRECAST CONCRETE BOX CULVERT 8'X3' (M273)	FOOT	314	314					
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	36	36					
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	322		322				
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	58	58					
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	192		192				
54206730	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 15"	FOOT	140		140				
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	40	40					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4		4				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7	4	3				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	4	2				

*SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.

SCALE : NONE