

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	12
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. RS-HPP-1805(00D)				
CONTRACT NO. 91368				

CODE NO.	ITEM	SAFETY CODE		2A		1E		1F	
		CONSTRUCTION CODE		J000	J000	Y030	Y030	Y031	Y031
		UNIT	TOTAL QUANTITY	ROADWAY CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	ROADWAY SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY	ROADWAY LIGHTING CHAMPAIGN SECTION 100% CITY	ROADWAY LIGHTING SAVOY SECTION 100% VILLAGE	TRAFFIC SIGNALS CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	TRAFFIC SIGNALS SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY
* X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	105	63	42				
* X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	2	1	1				
△ * X8250011	LIGHTING CONTROLLER, LOCATION NO. 1	L SUM	1			1			
△ * X8250012	LIGHTING CONTROLLER, LOCATION NO. 2	L SUM	1				1		
△ * X8250013	LIGHTING CONTROLLER, LOCATION NO. 3	L SUM	1				1		
△ * X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,520					750	770
△ * X8760100	PEDESTRIAN PUSH-BUTTON POST, UNPAINTED ALUMINUM, TYPE II	EACH	4						4
* XX002093	REMOVAL OF EXISTING RIPRAP	SQ YD	64	64					
* XX002998	RESTRICTED DEPTH MANHOLES, 4"-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	7		7				
△ * XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	1					1	
* 54247090	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	4		4				
* XX004735	RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	9	2	7				
△ * XX004921	PEDESTRIAN PUSH-BUTTON, SPECIAL	EACH	4					4	
* XX005400	RESTRICTED DEPTH MANHOLES, 8"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2				
△ * XX005428	INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	4					4	
* XX005473	STORM SEWERS TYPE 1 WATER MAIN QUALITY PIPE 30"	FOOT	160	160					
* XX005483	RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1		1				
△ * XX005928	TRAFFIC SIGNAL POST, 10 FOOT (SPECIAL)	EACH	2					2	
△ * XX005929	TRAFFIC SIGNAL POST, 14 FOOT (SPECIAL)	EACH	2					2	
* XX006440	RESTRICTED DEPTH MANHOLES, 5"-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	1		1				
△ * XX006444	MULCH, SPECIAL	ACRE	3.6	0.2	3.4				
* XX006582	BRICK SIGN AND CONCRETE FOUNDATION REMOVAL	L SUM	1		1				
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.50	0.50				
* Z0022800	FENCE REMOVAL	FOOT	95		95				
* Z0023900	FILLING EXISTING WELLS	EACH	1		1				
* Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	1		1				
△ * Z0059600	SANITARY SEWER, TYPE 2 8"	FOOT	12		12				
* Z0065900	SPECIAL DITCH CHECKS	EACH	3	1	2				
Y080 * Z0076600	TRAINEES	HOUR	500						
* XX007732	PRECAST CONCRETE BOX CULVERT 10'X2', SPECIAL	FOOT	540	540					
* XX006971	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 18"	FOOT	81		81				
* XX007733	SALVAGED AGGREGATE MATERIAL 8"	SQ YD	350	350					
* XX007734	SALVAGED AGGREGATE MATERIAL 12"	SQ YD	5,245	3,916	1,329				
* XX007735	SALVAGED AGGREGATE MATERIAL 24"	SQ YD	7,292	3,359	3,933				
△ * XX007736	JUNCTION BOX, SPECIAL (12"Wx 12"Lx12"D)	EACH	53			43	10		

*SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.

SCALE : NONE