

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	80% FED	20% STATE	80% FED	20% STATE	80% FED	20% STATE	100% CITY	50% STATE	50% CITY
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)		
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071			
				CONSTRUCTION CODE TYPE								
				1000-2A RURAL	1000-2A RURAL	1000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN				
M4248000	DETECTABLE WARNINGS											
M4400715	HOT-MIX ASPHALT SURFACE REMOVAL, 15MM	SQ M	39.7									
M4400725	HOT-MIX ASPHALT SURFACE REMOVAL, 25MM	SQ M	87,188									
M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SQ M	3,400	77,092								
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	212									
M4402000	PAVEMENT REMOVAL	SQ M	10,944									
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	11,736	8,933								
M4402040	COMBINATION CURB AND GUTTER REMOVAL	SQ M	8,669	5,539								
M4402050	SIDEWALK REMOVAL	METER	2,496	5,716								
M4405000	PAVED DITCH REMOVAL	SQ M	3,767									
M4420300	PAVEMENT PATCHING, TYPE I 300MM	METER	996		996						1,840	
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SQ M	322		322							
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	241		241							
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	23,183		21,926							
M5010521	REMOVE EXISTING CULVERTS	SQ M	23,183		22,376			21		1,236		
M5010522	PIPE CULVERT REMOVAL	METER	180		100			13		794		
M5030300	CLASS MS CONCRETE	METER	2,137		1,954			71		9		
M5030350	CONCRETE STRUCTURES	CU M	12.0					58		125		
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	CU M	4.9		4.9			12.0				
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	260		260							
M5401002	PRECAST CONCRETE BOX CULVERT 600MM x 450MM	KG	880		880							
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	15.1		15.1							
M5401010	PRECAST CONCRETE BOX CULVERT 900MM x 600MM	METER	15.6		15.6							
M5401020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M	METER	5.7		5.7							
M5401060	PRECAST CONCRETE BOX CULVERT 1.8M x 1.2M	METER	19.8		19.8							
M5402020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M (M273)	METER	25.2		25.2							
M5402035	PRECAST CONCRETE BOX CULVERT 1.5M x 0.9M (M273)	METER	30.6		30.6							
M5403220	EXPANSION BOLTS M20	METER	9.0		9.0							
M5421210	PIPE CULVERTS, TYPE 1 RCCP 375MM	EACH	206		206							
M5421215	PIPE CULVERTS, TYPE 1 RCCP 450MM	METER	126.5		110.5							
M5421225	PIPE CULVERTS, TYPE 1 RCCP 600MM	METER	66.0		53.5				16.0			
M5421235	PIPE CULVERTS, TYPE 1 RCCP 750MM	METER	118.5		118.5				12.5			
M5421240	PIPE CULVERTS, TYPE 1 RCCP 900MM	METER	32.5		32.5							
M5421260	PIPE CULVERTS, TYPE 1 RCCP 1500MM	METER	55.5		55.5							
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	METER	17.5		17.5							
M542C216	REINFORCED CONCRETE PIPE TEE, 375MM PIPE WITH 300MM RISER	EACH	1					1				
M542C220	REINFORCED CONCRETE PIPE TEE, 450MM PIPE WITH 300MM RISER	EACH	1		1							
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	2									
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	8					2				
M542C244	REINFORCED CONCRETE PIPE TEE, 900MM PIPE WITH 300MM RISER	EACH	5					8				
M542C248	REINFORCED CONCRETE PIPE TEE, 1050MM PIPE WITH 300MM RISER	EACH	7					5				
M542C328	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 375MM RISER	EACH	3					7				
M542C336	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 375MM RISER	EACH	1					3				
M542E012	END SECTIONS 300MM	EACH	1		1							
M542E016	END SECTIONS 375MM	EACH	1		1							
M542E020	END SECTIONS 450MM	EACH	104		102							
M542E024	END SECTIONS 525MM	EACH	82		70				2			
M542E028	END SECTIONS 600MM	EACH	14		14				12			
M542E032	END SECTIONS 675MM	EACH	48		48							
M542E036	END SECTIONS 750MM	EACH	6		6							
M542E044	END SECTIONS 900MM	EACH	12		12							
M542E048	END SECTIONS 1050MM	EACH	14		14							
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	4		4							
		EACH	12		10				2			

* SEE SPECIAL PROVISIONS

CONTINUED

PLT DATE = 11/7/2008
FILE NAME = H:\1420\1\res\Drawings\Drawings\0794533\SH1_004_sumsq_VB.dgn

H. M. & G. NO. 4420

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES

SCALE _____ DRAWN BY KOJ
DATE OCTOBER 28, 2008 CHECKED BY LWJ