F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE CULVERT SCHEDULE - CONTINUED

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS															PRECAST REINFORCED CONCRETE FLARED END SECTIONS						END SECTIONS								PIPE TEES			INLETS
				RCCP						CLASS D																							375 PIPE WITH 300 RISER	600 PIPE WITH 375 RISER	750 PIPE WITH 375 RISER	TYPE A, TY 8 GRATE
				TYPE 1 375	TYPE 1 450	TYPE 1 600	TYPE 1 750	TYPE 1 900	TYPE 1 1500	TYPE 1 300	TYPE 1 375	TYPE 1 450	TYPE 1 525	TYPE 1 600	TYPE 1 675	TYPE 1 750	TYPE 1 900	TYPE 1 1050	375	450	600	750	900	1500	300	375	450	525	600	675	750	900	1050				
STATION	RT/LT /AR		CUBIC METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA 7+509.000	LT	PIPE CULVERTS	3.73				9.14															2														
STA 7+537.000	LT	PIPE CULVERTS	11.22				23.16															2														
STA 7+682.000	RT	PIPE CULVERTS									11.58															2										
STA 7+755.000	LT	PIPE CULVERTS													8.84															2						
STA 8+063.000	RT	PIPE CULVERTS									21.03															2										
STA 8+161.200	RT	PIPE CULVERTS												11.58															2							
STA 8+296.000	LT	PIPE CULVERTS															10.06															2				
STA 8+311.000	RT	PIPE CULVERTS												14.33															2							
STA 8+456.000	LT	PIPE CULVERTS														10.06															2					
STA 8+456.000	RT	PIPE CULVERTS												10.67															2							
STA 8+563.000	LT	PIPE CULVERTS											10.97														2									
STA 8+607.000	RT	PIPE CULVERTS									14.33															2										
STA 8+613.500	LT	PIPE CULVERTS											14.94														2									
STA 8+634.000	LT	PIPE CULVERTS											14.63														2									
STA 8+651.000	RT	PIPE CULVERTS									15.85															2										
STA 8+669.000	RT	PIPE CULVERTS									15.54															2										
STA 8+724.500	RT	PIPE CULVERTS									10.67															2										
STA 8+739.700	LT	PIPE CULVERTS									13.11															2										
STA 8+749.000	RT	PIPE CULVERTS									12.19															2										
STA 8+770.500	LT	PIPE CULVERTS									14.94															2										
STA 8+778.500	RT	PIPE CULVERTS									14.02															1										
STA 8+785.400	RT	INLET																																		1
STA 8+792.000	LT	PIPE CULVERTS									13.72															2										
STA 8+793.300	RT	PIPE CULVERTS									16.46															1										
STA 8+841.000	RT	PIPE CULVERTS									21.03															2										
STA 8+843.000	LT	PIPE CULVERTS										19.81															2									
STA 8+869.500	RT	PIPE CULVERTS									20.12															2										
STA 8+949.000	RT	PIPE CULVERTS									17.68															2										
STA 9+073.000	LT	PIPE CULVERTS										10.97															2									
STA 9+192.500	RT	PIPE CULVERTS										17.68															2									
STA 9+682.500	RT	PIPE CULVERTS										12.19															2									
STA 9+707.500	RT	PIPE CULVERTS										16.15															2									
STA 10+321.500	RT	PIPE CULVERTS												11.58															2							
STA 10+329.000	LT	PIPE CULVERTS												18.90															2							
STA 10+500.000	LT	PIPE CULVERTS	9.99			19.81															2															
STA 10+559.500	RT	PIPE CULVERTS												17.68															2							
STA 10+705.000	LT	PIPE CULVERTS												14.63															2							
STA 10+732.000	LT	PIPE CULVERTS												9.41															2					1		
STA 10+736.079	RT	PIPE CULVERTS	4.07			18.70															2															
STA 10+736.075	LT	INLET									2.44															1										1
STA 10+740.000	LT	PIPE CULVERTS												8.65																						
STA 10+765.500	LT	PIPE CULVERTS										11.89															2									
STA 10+784.800	LT	PIPE CULVERTS										21.34															2									
STA 10+819.600	RT	PIPE CULVERTS												14.63															2							
STA 10+824.000	LT	PIPE CULVERTS										14.63															2									
STA 10+864.000	RT	PIPE CULVERTS										14.33															2									
STA 10+915.500	LT	PIPE CULVERTS										10.67															2									
STA 10+920.500	RT	PIPE CULVERTS										10.06															2									
STA 11+146.500	LT	PIPE CULVERTS									14.02															2										
STA 11+246.000	RT	PIPE CULVERTS									15.54															2										
STA 11+306.500	LT	PIPE CULVERTS									13.72															2										
STA 11+571.600	RT	PIPE CULVERTS	17.09	33.83									2																							
STA 11+756.500	LT	PIPE CULVERTS									26.52															2										
STA 11+778.500	LT	RCP. C. EXTEN.						6.709															1													
STA 11+778.500	RT	RCP. C. EXTEN.						6.095															1													
STA 11+880.000	RT	PIPE CULVERTS									23.16															2										
STA 11+914.500	RT	PIPE CULVERTS									19.51															2										

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE CULVERT SCHEDULE

SCALE | DRAWN BY KOJ
DATE APRIL 18, 2008 | CHECKED BY RGH

H. M. & G. NO. 4420

PLOT DATE = 4/18/2008
FILE NAME = H:\4420\70027_sch_pipe culverts.dgn