

PAVEMENT MARKING SCHEDULE						
STATION TO STATION	LENGTH	POLYUREA PAVEMENT MARKING - LINE 4" (YELLOW)	POLYUREA PAVEMENT MARKING - LINE 4" (WHITE)	POLYUREA PAVEMENT MARKING - LINE 6" (WHITE)	WORK ZONE PAVEMENT MARKING REMOVAL	
					FEET	SQ FT
I-70 WB						
1591+80.00 TO 1593+10.00	130	130	130	32.5		173
1593+10.00 TO 1596+13.00	303	303	303	75.8		404
1596+13.00 TO 1597+43.00	130	130	130	32.5		173
1597+43.00 TO 1610+33.67	1291	1290.7	1290.7	322.7		860
1610+33.67 BK = 90+55.19 AH STATION EQUATION						
90+55.19 TO 117+25.00	2670	2669.8	2669.8	667.5		1780
117+25.00 TO 118+55.00	130	130	130	32.5		173
118+55.00 TO 128+48.00	993	993	993	248.3		1324
128+48.00 TO 129+78.00	130	130	130	32.5		173
129+78.00 TO 135+45.00	567	567	567	141.8		378
135+45.00 TO 136+75.00	130	130	130	32.5		173
136+75.00 TO 141+29.00	454	454	454	113.5		605
141+29.00 TO 142+59.00	130	130	130	32.5		173
142+59.00 TO 147+59.00	500	500	500	125.0		333
147+59.00 TO 157+59.00	1000	1000	1000	250.0		667
I-70 EB						
1576+97.00 TO 1586+97.00	1000	1000	1000	250.0		667
1586+97.00 TO 1591+97.00	500	500	500	125.0		333
1591+97.00 TO 1593+27.00	130	130	130	32.5		173
1593+27.00 TO 1596+40.00	313	313	313	78.3		417
1596+40.00 TO 1597+70.00	130	130	130	32.5		173
1597+70.00 TO 1610+33.67	1264	1263.7	1263.7	315.9		842
1610+33.67 BK = 90+55.19 AH STATION EQUATION						
90+55.19 TO 117+38.00	2683	2682.8	2682.8	670.7		1789
117+38.00 TO 118+68.00	130	130	130	32.5		173
118+68.00 TO 127+86.00	918	918	918	229.5		1224
127+86.00 TO 129+16.00	130	130	130	32.5		173
129+16.00 TO 134+82.00	566	566	566	141.5		377
134+82.00 TO 136+27.00	130	130	130	32.5		173
136+27.00 TO 140+66.00	439	439	439	109.8		585
140+66.00 TO 141+96.00	130	130	130	32.5		173
TOTAL	17020	17020	17020	4256		14666

BASE COURSE WIDENING						
LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE B	PAVED SHOULDER REMOVAL	PCC BASE COURSE WIDENING, 10'	SHOULDER RUMBLE STRIPS		
				TON	SQ YD	FOOT
I-70 WB						
1591+60.00 TO 1594+34.00	17.3	152.2	152.2	274.0		
1595+41.00 TO 1597+63.00	14.0	123.3	123.3	222.0		
117+05.00 TO 119+95.00	18.3	161.1	161.1	290.0		
121+11.00 TO 125+90.00	30.3	266.1	266.1	479.0		
127+64.00 TO 129+98.00	14.8	130.0	130.0	234.0		
135+25.00 TO 138+15.00	18.3	161.1	161.1	290.0		
140+45.00 TO 142+79.00	14.8	130.0	130.0	234.0		
1591+60.00 TO 1594+25.00	16.8	147.2	147.2	265.0		
1595+34.00 TO 1597+63.00	14.5	127.2	127.2	229.0		
117+05.00 TO 119+81.00	17.5	122.7	153.3	276.0		
120+92.00 TO 125+64.00	29.9	209.8	262.2	472.0		
127+40.00 TO 129+98.00	16.3	114.7	143.3	258.0		
135+25.00 TO 137+86.00	16.5	116.0	145.0	261.0		
140+21.00 TO 142+79.00	16.3	114.7	143.3	258.0		
I-70 EB						
1591+77.00 TO 1594+00.00	14.1	123.9	123.9	223.0		
1595+16.00 TO 1597+90.00	17.3	152.2	152.2	274.0		
117+17.00 TO 119+37.00	13.9	122.2	122.2	220.0		
120+49.00 TO 124+86.00	27.6	242.8	242.8	437.0		
126+61.00 TO 129+36.00	17.4	152.8	152.8	275.0		
134+82.00 TO 137+02.00	13.9	122.2	122.2	220.0		
139+41.00 TO 142+16.00	17.4	152.8	152.8	275.0		
1591+77.00 TO 1594+07.00	14.6	102.2	127.8	230.0		
1595+16.00 TO 1597+90.00	17.3	121.8	152.2	274.0		
117+17.00 TO 119+51.00	14.8	104.0	130.0	234.0		
120+62.00 TO 125+10.00	28.3	199.1	248.9	448.0		
126+85.00 TO 129+36.00	15.9	111.6	139.4	251.0		
134+82.00 TO 137+36.00	16.1	112.9	141.1	254.0		
139+70.00 TO 142+16.00	15.6	109.3	136.7	246.0		
TOTALS	500.0	4006.0	4391.0	7903.0		

AGGREGATE SHOULDERS, TYPE B			TON
I-70 WB			
1591+60.00 TO 1594+25.00			10.3
1595+34.00 TO 1597+63.00			8.9
117+05.00 TO 119+81.00			10.7
120+92.00 TO 125+64.00			18.3
127+40.00 TO 129+98.00			10.0
135+25.00 TO 137+86.00			10.1
140+21.00 TO 142+79.00			10.0
I-70 EB			
1591+77.00 TO 1594+07.00			8.9
1595+16.00 TO 1597+90.00			10.0
117+17.00 TO 119+51.00			9.1
120+62.00 TO 125+10.00			17.3
126+85.00 TO 129+36.00			9.7
134+82.00 TO 137+36.00			9.8
139+70.00 TO 142+16.00			9.5
TOTAL			153

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -
o:\pwork\pwork\swartzw\dms50711\sh...	h_94993.dgn	DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 10/17/2008		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	FAYETTE	59	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 94993	

Rev. 12-19-08

\* D-7 BRIDGE DECK REPAIRS