

# SUMMARY OF QUANTITIES

SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9393	05-00025-00-TL	MADISON	135	3
STA.		TO STA.		

CONTRACT NO. 97352

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	31
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24
20200100	EARTH EXCAVATION	CU YD	2,439
20400800	FURNISHED EXCAVATION	CU YD	4,660
20800150	TRENCH BACKFILL	CU YD	138
25000210	SEEDING, CLASS 2A	ACRE	2.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225
25100115	MULCH, METHOD 2	ACRE	2.5
25100630	EROSION CONTROL BLANKET	SQ YD	1,037
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	2.5
28000300	TEMPORARY DITCH CHECK	EACH	1
28000400	PERIMETER EROSION BARRIER	FOOT	1,918
28000500	INLET AND PIPE PROTECTION	EACH	33
28100107	STONE RIPRAP, CLASS A4	SQ YD	20
28200200	FILTER FABRIC	SQ YD	20
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	2,264
30201500	LIME	TON	44
31102200	SUB-BASE GRANULAR MATERIAL, TYPE C 5"	SQ YD	4,512
31102300	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	1,307
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	391
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	104
35400200	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 7"	SQ YD	95
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	232
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,757
40600300	AGGREGATE (PRIME COAT)	TON	32
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	745
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	320
40600990	TEMPORARY RAMP	SQ YD	240
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3,790
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,852
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	45
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	430
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,081
42400800	DETECTABLE WARNINGS	SQ FT	48
44000100	PAVEMENT REMOVAL	SQ YD	82
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	759
44000400	GUTTER REMOVAL	FOOT	1,007
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	619
44000600	SIDEWALK REMOVAL	SQ FT	638
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,932
44200924	CLASS B PATCHES, TYPE III, 7"	SQ YD	19
44200926	CLASS B PATCHES, TYPE IV, 7"	SQ YD	29

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
44201789	CLASS D PATCHES, TYPE II, 12"	SQ YD	14
44213200	SAW CUTS	FOOT	145
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8,601
48100500	AGGREGATE SHOULDERS, TYPE A, 6"	SQ YD	621
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	292
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5,243
50104400	CONCRETE HEADWALL REMOVAL	EACH	8
50105220	PIPE CULVERT REMOVAL	FOOT	653
50901760	PIPE HANDRAIL	FOOT	73
54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	17
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	135
54201279	PIPE CULVERTS, TYPE 2, RCCP 24"	FOOT	27
54201291	PIPE CULVERTS, TYPE 2, RCCP 36"	FOOT	103
54201297	PIPE CULVERTS, TYPE 2, RCCP 42"	FOOT	11
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1
54213870	STEEL END SECTIONS 15"	EACH	8
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2
54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42"	EACH	1
54223447	REMOVE AND RELAY PIPE CULVERTS 12"	FOOT	31
54248510	CONCRETE COLLAR	CU YD	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	280
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	449
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	151
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	75
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	49
55100500	STORM SEWER REMOVAL, 12"	FOOT	24
60219530	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1, FRAME, CLOSED LID	EACH	1
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	1
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	3
60240327	INLETS, TYPE B, TYPE 23 FRAME AND GRATE	EACH	1
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	4
60242500	INLETS, SPECIAL, NO. 1	EACH	5
60242600	INLETS, SPECIAL, NO. 2	EACH	1
60242700	INLETS, SPECIAL, NO. 3	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	4
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	20
60602500	CONCRETE GUTTER, TYPE A	FOOT	80
60602800	CONCRETE GUTTER, TYPE B	FOOT	226
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	351
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,511

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

## SUMMARY OF QUANTITIES

US 40 AND  
TROY-O'FALLON ROAD IMPROVEMENTS  
CITY OF TROY  
MADISON COUNTY, ILLINOIS