

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN			ROADWAY 0004	80% FED 20% STATE	13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE	100% CRYSTAL LAKE FIRE DEPT.
				ROADWAY 0004	T.S. SIGNAL 0021	EVP 0021				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1370	1370						
55101300	STORM SEWER REMOVAL 27"	FOOT	79	79						
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3						
60107600	PIPE UNDERDRAINS 4"	FOOT	467	467						
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	47	47						
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	8	8						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10						
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	9	9						
60500060	REMOVING INLETS	EACH	2	2						
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8.1	8.1						
60600605	CONCRETE CURB, TYPE B	FOOT	100	100						
60608582	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4, 24	FOOT	1712	1712						
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75						

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN			ROADWAY 0004	80% FED 20% STATE	13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE	100% CRYSTAL LAKE FIRE DEPT.
				ROADWAY 0004	T.S. SIGNAL 0021	EVP 0021				
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	25	25						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3						
* 63200310	GUARDRAIL REMOVAL	FOOT	226	226						
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	5000	5000						
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
67100100	MOBILIZATION	L SUM	1	1						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
* SPECIALTY ITEMS										

FILE NAME: P114205-DESIGN.dgn	USER NAME: abrcuah	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. RTE. 176 AT SMITH ROAD SUMMARY OF QUANTITIES	F.A.P. RTE. 335	SECTION 146N-2	COUNTY MCHENRY	TOTAL SHEETS 65	SHEET NO. 5		
PLOT SCALE: 1/8" = 1'	PLOT DATE: 11/1/2013	DRAWN: -	REVISED: -			SCALE: 1" = 100'	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
		CHECKED: -	REVISED: -			CONTRACT NO. 60K20						
		DATE: -	REVISED: -			Rev. 1-9-14						