

COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12. TABLE WITH COLUMNS: FROM, TO, LENGTH (FEET), STATION, SIDE. ROWS: DRIVEWAYS (63+40 to 126+61), TOTAL 1,197.

CONCRETE MEDIAN TSB-6 (DOWELLED). TABLE WITH COLUMNS: STATION, LENGTH (FEET), AREA (SQ. FT.). ROWS: US RTE 12/20/45 (65+25 to 73+56), TOTAL QUANTITY = 6,510.

CONCRETE MEDIAN, TYPE SB-6.06. TABLE WITH COLUMNS: STATION, LENGTH (FEET), AREA (SQ. FT.). ROWS: JOLIET ROAD (110+39 to 125+37), TOTAL QUANTITY = 179.

CORRUGATED MEDIAN (MODIFIED). TABLE WITH COLUMNS: STATION, LENGTH (FEET), AREA (SQ. FT.). ROWS: US RTE 12/20/45 (70+90 to 73+26), TOTAL QUANTITY = 352.

TUBULAR TRAFFIC SIGN POST. TABLE WITH COLUMNS: STATION, OFFSET (FEET), QUANTITY (EACH). ROWS: US RTE 12/20/45 (66+29 to 78+50), TOTAL QUANTITY = 13.

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH. TABLE WITH COLUMNS: STATION, AREA (SQ. YD.). ROWS: US RTE 12/20/45 (74+50 to 76+50), JOLIET ROAD (118+50 to 125+50), TOTAL QUANTITY = 5810.

SIGN SCHEDULE. TABLE WITH COLUMNS: STATION, SIDE, SIGN #, WIDTH (IN), DEPTH (IN), SIGN PANEL, TYPE 1 (SQ. FT.), POST LENGTH (FT), TYPE B. ROWS: JOLIET ROAD (111+88 to 127+58), US RTE 12/20/45 (63+15 to 80+76), TRAFFIC SIGNALS, TOTAL 390, 475.

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL). TABLE WITH COLUMNS: STATION, OFFSET (FEET), QUANTITY (EACH). ROWS: US RTE 12/20/45 (63+21 to 128+81), JOLIET ROAD (110+51 to 126+61), TOTAL 22.

HANDHOLE TO BE ADJUSTED. TABLE WITH COLUMNS: STATION, OFFSET (FEET), QUANTITY (EACH). ROWS: US RTE 12/20/45 (65+80 to 127+64), JOLIET ROAD (116+05 to 124+60), TOTAL 5.

AGGREGATE SUBGRADE IMPROVEMENT 12 INCH. TABLE WITH COLUMNS: STATION, AREA (SQ. YD.). ROWS: US RTE 12/20/45 (62+21.50 to 72+44.26), JOLIET ROAD (108+04.50 to 128+95.50), ISLANDS (119+30 to 120+48), TOTAL QUANTITY = 6,521.

HEAVY DUTY HANDHOLE TO BE ADJUSTED. TABLE WITH COLUMNS: STATION, OFFSET (FEET), QUANTITY (EACH). ROWS: US RTE 12/20/45 (63+41 to 81+79), TOTAL 2.

INLET FILTERS. TABLE WITH COLUMNS: STATION, SIDE, QUANTITY. ROWS: US RTE 12/20/45 STAGE 1 (62+10 to 84+20), JOLIET RD STAGE 1 (107+95 to 128+62), US RTE 12/20/45 STAGE 2 (63+80 to 66+50), TOTAL QUANTITY = 81.