

| SUMMARY OF QUANTITIES | | | URBAN | CONSTRUCTION TYPE CODE | | | | | | | | | | | | | | | | | | | |
|-----------------------|---|-------|------------------|--|---|---|--|---|---|--|------------------------------|--|--|--|--|--|--|--|--|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | LOC. 1 90% FED. 10% STATE 0004 ROADWAY | LOC. 1 7.5% STATE 2.5% LYONS 0021 TRF. SIG. | LOC. 2 90% FED. 5% STATE 5% LYONS 0021 TRF. SIG. | LOC. 3 90% FED. 10% STATE 0021 TRF. SIG. | LOC. 4 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG. | LOC. 5 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG. | 90% FED. 10% STATE 0021 INTER- CONNECT | 100% LYONS 0021 EVP | | | | | | | | | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 28 | 28 | | | | | | | | | | | | | | | | | | | |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE. MIX "F", N90 | TON | 736 | 736 | | | | | | | | | | | | | | | | | | | |
| 42001300 | PROTECTIVE COAT | SO YD | 308 | 205 | | | 25 | 56 | 22 | | | | | | | | | | | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SO FT | 1775 | 1180 | | | 102 | 371 | 122 | | | | | | | | | | | | | | |
| 42400800 | DETECTABLE WARNINGS | SO FT | 246 | 106 | | | 52 | 37 | 51 | | | | | | | | | | | | | | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SO YD | 7501 | 7501 | | | | | | | | | | | | | | | | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SO YD | 11 | 11 | | | | | | | | | | | | | | | | | | | |
| 44000600 | SIDEWALK REMOVAL | SO FT | 1484 | 925 | | | 66 | 371 | 122 | | | | | | | | | | | | | | |
| 44002216 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4" | SO YD | 125 | 125 | | | | | | | | | | | | | | | | | | | |
| 44003100 | MEDIAN REMOVAL | SO FT | 455 | 455 | | | | | | | | | | | | | | | | | | | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SO YD | 27 | 27 | | | | | | | | | | | | | | | | | | | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SO YD | 7 | 7 | | | | | | | | | | | | | | | | | | | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SO YD | 74 | 74 | | | | | | | | | | | | | | | | | | | |
| 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | SO YD | 11 | 11 | | | | | | | | | | | | | | | | | | | |
| 60300105 | FRAMES AND GRATES TO BE ADJUSTED | EACH | 4 | 4 | | | | | | | | | | | | | | | | | | | |
| | ● SPECIALTY ITEM | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | |
|--|------------------------|------------|-----------|---|-----------------------|--------------------|----------------------------------|---|--------------|-----------|
| FILE NAME : c:\pwork\pwork\pwork\ltd0316559-F100212-1tr-2 | USER NAME : pascencal | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| PLOT SCALE : 1/8" = 1'-0" | PLOT DATE : 10/18/2011 | DRAWN - | REVISED - | | | 372 | 2012-0471 | COOK | 63 | 5 |
| | | CHECKED - | REVISED - | | | CONTRACT NO. 60V34 | | | | |
| | | DATE - | REVISED - | | | SCALE: | SHEET NO. OF SHEETS STA. TO STA. | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | |