

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE																		
CODE NO	ITEM	UNIT		LOC. 1 90% FED. 10% STATE 0004 ROADWAY	LOC. 1 90% FED. 7.5% STATE 2.5% LYONS 0021 TRF. SIG.	LOC. 2 90% FED. 5% STATE 5% LYONS 0021 TRF. SIG.	LOC. 3 90% FED. 10% STATE 0021 TRF. SIG.	LOC. 4 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	LOC. 5 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	90% FED. 10% STATE 0021 INTER- CONNECT	100% LYONS 0021 EVP											
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	5		1	1	1	1	1													
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	5264		836	620	1296	816		1696												
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	242		58	45	88	51														
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	229		48	53	40	88														
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1465		454	297	462	252														
81400100	HANDHOLE	EACH	19		3	5	6	4		1												
81400200	HEAVY-DUTY HANDHOLE	EACH	13		5	2	4	2														
81400300	DOUBLE HANDHOLE	EACH	6		2	1	2	1														
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2							1	1											
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5		1	1	1	1	1													
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4723							4723												
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3105		1323		1392	228	162													
	● SPECIALTY ITEM																					

12

FILE NAME =	USER NAME = plascencal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLT SCALE = 1000000' / 1"	DRAWN -	REVISED -	372			2012-0471	COOK	63	8	
PLT DATE = 10/18/2013	CHECKED -	REVISED -	CONTRACT NO. 60V34							
	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.			