SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE LOC. 1 90% FED. 10% STATE 0004 ROADWAY	LOC. 1 90% FED. 7.5% STATE 2.5% LYONS 0021 TRF. SIG.	LOC. 2 90% FED. 5% STATE 5% LYONS 0021 TRF. SIG.	LOC. 3 90% FED. 10% STATE 0021 TRF. SIG.	LOC. 4 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	LOC. 5 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	90% FED. 10% STATE 0021 INTER-CONNECT	100% LYONS 0021 EVP
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	4730		1675		1776	598	169		512
	14 3C										
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	7083		1822	2020	1548	1693			
	14 5C										
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.	FOOT	4077		1512	681	1570	314			
	14 7C										
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.	FOOT	8332		2143	1535	3647	1007			
	14 1 PAIR										
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.	FOOT	350		62	32	70	186			
	6 2 C										
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT	FOOT	2359		603	500	638	618			
	GROUNDING CONDUCTOR, NO. 6 1C										
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	3			2			1		
	14 FT.										
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	12		4	1	4	1	2		
	16 FT.										
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL	EACH	1					1			
	18 FT.										
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1					1			
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1					1			
	* SPECIALTY ITEM										

FILE NAME = c:\pw_work\pwidot\passerella\d0316539\f1082ll-str-SQ.dgn	USER NAME = passerella	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1000.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/18/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	2012-0471	COOK	63	9
		CONTRACT NO. 60V34		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT