

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE																	
CODE NO	ITEM	UNIT		LOC. 1 90% FED. 10% STATE 0004 ROADWAY	LOC. 1 90% FED. 7.5% STATE 2.5% LYONS 0021 TRF. SIG.	LOC. 2 90% FED. 5% STATE 5% LYONS 0021 TRF. SIG.	LOC. 3 90% FED. 10% STATE 0021 TRF. SIG.	LOC. 4 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	LOC. 5 90% FED. 6.7% STATE 3.3% LYONS 0021 TRF. SIG.	90% FED. 10% STATE 0021 INTER- CONNECT	100% LYONS 0021 EVP										
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2	2																	
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	3		2	1															
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1					1													
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1																
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	3	2		1															
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1															
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2		1	1															
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	52	16	12	16	8														
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	16	4	4	4	4														
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	161.5	47	40.5	40.5	33.5														
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26		13	13															
87900200	DRILL EXISTING HANDHOLE	EACH	2						2												
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	31	6	8	8	5	4													
	* SPECIALTY ITEM																				