

FILE PATH: \\pva\360229-purd\ascenonline\local\wsc\6029\Documents\61-Arrivals\Truss\taison\6256\138-Circle\Shane_11\6029_CAD\206-Roadway\Streets\60621-Contract\60629-shr-500.dgn

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER
				90% FED		90% FED	90% FED	90% FED
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE
				0004	0004	0011	0021	0044
URBAN	URBAN	016-1708	URBAN	URBAN				
50800105	REINFORCEMENT BARS	POUND	292,640			292,640		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	173,600	15,800		157,800		
51500100	NAME PLATES	EACH	1			1		
51602000	PERMANENT CASING	FOOT	1,554			1,554		
* 51603000	DRILLED SHAFT IN SOIL	CU YD	1,318.9			1,318.9		
* 51604000	DRILLED SHAFT IN ROCK	CU YD	38.2			38.2		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18			18		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	9			9		
52100520	ANCHOR BOLTS, 1"	EACH	18			18		
52100530	ANCHOR BOLTS, 1 1/4"	EACH	36			36		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	100	100				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	15	15				
55100400	STORM SEWER REMOVAL 10"	FOOT	9	9				
58700300	CONCRETE SEALER	SQ FT	9,022	900		8,122		

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM



D:\6029-shr-300.dgn
 USER NAME = JTRubley
 PLOT SCALE = 20.0000' / in.
 PLOT DATE = 11/6/2013

DESIGNED - JLV
 DRAWN - BAW
 CHECKED - JMG
 DATE - 10/30/2013
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 5 OF 17 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	10
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	