	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
					ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER
					90% FED		90% FED	90% FED	90% FED
					10% STATE	100% STATE	10% STATE	10% STATE	10% STATE
					0004	0004	0011	0021	0044
					URBAN	URBAN	016-1708	URBAN	URBAN
*	81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	22				22	
*	81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	14				14	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	3				3	
*	81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	190				190	
*	81603081	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	340				340	
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,560				1,560	
*	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	265				265	
*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	530				530	
*	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	135				135	
*	81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	400				400	
*	81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	625				625	
*	82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	16				16	
*	82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8				8	
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12				12	

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICPATING ITEM

TranSystems

0160W29-sht-SCO.dgn	DESIGNED - JLV	REVISED -	
USER NAME = JTRubley	DRAWN - BAW	REVISED -	
PLOT SCALE = 20.0000 ' / in.	CHECKED - JMG	REVISED -	
PLOT DATE = 11/6/2013	DATE - 10/30/2013	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET 10 OF 17 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	15
		CONTRACT NO. 60W29		
	ILLINOIS	FED. AID PROJECT		

FILE PATH = pw:\\398839-pwint.accenture.local:PWEC60030\Documents\01 Americas\Transportation\60269938 Cicero\Phase II\0260_C00\0206_Roadway\Sheets\160W29_Contract\0160W29-sht-SCO.dgn