

**REMOVAL SCHEDULE**

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE BARRIER REMOVAL	APPROACH SLAB REMOVAL	FENCE REMOVAL	GUARDRAIL REMOVAL
	UNIT	UNIT	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ FT	FOOT	SQ YD	FOOT	FOOT
PEORIA STREET	318	949	63	722	95	258	443	15,588		184	324	276
I-290 WB				276			92		186			
I-290 EB				576					321			
<b>TOTAL</b>	<b>318</b>	<b>949</b>	<b>63</b>	<b>1,574</b>	<b>95</b>	<b>258</b>	<b>535</b>	<b>15,588</b>	<b>507</b>	<b>184</b>	<b>324</b>	<b>276</b>

**TREE REMOVAL SCHEDULE**

STATION	OFFSET	LT/RT	NO. STEMS	SIZE DIAMETER	TREE REMOVAL 6-15	TREE REMOVAL OVER 15	TREE PRUNING 1 - 10	TREE PRUNING OVER 10
				INCH	UNIT	UNIT	EACH	EACH
3700+15.42	25.25	LT	1	18				1
3700+15.46	53.09	LT	1	10			1	
3700+16.37	25.45	RT	1	20				1
3700+30.30	91.42	RT	3	6,7,12		25		
3700+34.22	59.00	RT	3	6,6,6		18		
3700+39.50	79.40	RT	3	6,6,9		21		
3700+45.16	63.42	LT	5	6,6,6,6,6		30		
3700+49.29	55.16	RT	5	6,6,6,6,6		30		
3700+53.73	75.13	RT	4	5,8,9,9		31		
3700+59.48	133.29	LT	1	7	7			
3700+59.77	58.02	LT	4	4,4,4,4		16		
3700+59.95	122.32	LT	1	8	8			
3700+60.02	109.36	LT	1	8	8			
3700+60.11	97.78	LT	1	10	10			
3700+64.62	52.20	RT	2	8,8		16		
3700+66.62	140.54	LT	1	14	14			
3700+69.01	73.35	RT	1	9	9			
3700+69.96	132.92	LT	1	6	6			
3700+72.44	109.55	LT	1	9	9			
3700+72.55	123.70	LT	1	9	9			
3700+74.06	51.97	LT	3	10,10,10		30		
3700+78.21	77.62	LT	3	4,5,11		20		
3700+80.12	49.02	RT	2	8,8		16		
3700+85.52	49.49	LT	3	4,4,4	12			
3700+85.66	69.31	RT	3	5,7,11		23		
3700+92.13	73.30	LT	3	8,10,12		30		
3700+96.23	44.66	RT	4	8,8,8,8		32		
3700+99.77	46.06	LT	3	8,8,8		24		
3701+05.87	71.23	LT	3	3,3,3	9			
3701+11.43	41.22	RT	4	8,8,8,8		32		
3701+16.12	41.83	LT	3	6,6,6		18		
3701+18.52	62.28	RT	2	9,10		19		
3701+27.43	38.28	RT	3	6,6,6		18		
3701+31.86	38.74	LT	3	6,6,6		18		
3701+32.56	59.57	RT	3	6,9,11		26		
3701+35.99	135.64	LT	1	9	9			
3701+37.89	63.45	LT	4	5,6,7,14		32		
3701+42.18	35.08	RT	4	8,8,8,8		32		
3701+48.13	34.46	LT	4	8,8,8,8		32		
3701+49.05	56.55	RT	2	8,12		20		
3701+58.95	30.70	RT	3	6,6,6		18		
3701+63.88	52.52	RT	2	6,9	15			

STATION	OFFSET	LT/RT	NO. STEMS	SIZE DIAMETER	TREE REMOVAL 6-15	TREE REMOVAL OVER 15	TREE PRUNING 1 - 10	TREE PRUNING OVER 10
				INCH	UNIT	UNIT	EACH	EACH
3701+64.02	30.40	LT	4	8,8,8,8		32		
3701+68.51	56.18	LT	3	9,10,11		30		
3701+74.23	28.37	RT	3	6,6,6		18		
3701+78.32	27.02	LT	4	6,6,6,6		24		
3701+80.62	49.23	RT	3	6,8,11		25		
3701+83.94	52.93	LT	2	3,3	6			
3701+93.83	23.83	LT	4	6,6,6,6		24		
3701+95.58	44.95	RT	3	5,6,10		21		
3701+99.25	49.56	LT	3	3,3,4	10			
3702+08.12	20.22	LT	2	6,6	12			
3702+09.21	42.26	RT	3	5,7,9		21		
3702+13.55	58.55	RT	3	6,6,9		21		
3702+14.38	45.92	LT	3	5,8,8		21		
3702+15.68	17.92	RT	2	6,6	12			
3702+23.11	39.33	RT	2	4,4	8			
3702+23.59	17.23	LT	2	6,6	12			
3702+25.17	58.73	LT	4	2,3,4,4	13			
3702+30.05	41.86	LT	2	3,6	9			
3702+32.05	66.92	RT	4	5,6,6,7				1
3702+34.27	40.04	RT	3	4,5,5	14			
3702+36.55	53.91	RT	4	2,3,3,4	12			
3702+40.31	66.83	RT	6	2,3,3,3,4,4				1
3702+40.25	38.92	LT	6	3,3,4,4,4,5		23		
3702+42.94	48.95	LT	6	2,2,5,5,5,6		25		
3702+43.48	61.34	LT	5	3,3,3,4,6		19		
3702+49.41	72.96	LT	3	5,6,7		18		
3705+09.32	33.04	RT	1	10	10			
3705+16.01	65.13	LT	1	7			1	
3705+25.00	63.51	LT	1	19				1
3705+26.06	37.47	LT	1	12	12			
3705+26.67	56.70	RT	1	6	6			
3705+30.05	60.98	LT	1	19				1
3705+34.17	73.29	RT	1	5			1	
3705+36.37	60.15	RT	2	4,4	8			
3705+39.96	42.77	RT	1	9	9			
3705+43.76	57.86	LT	1	3			1	
3705+68.55	22.01	LT	1	10	10			
3706+08.85	21.59	LT	1	6	6			
3706+17.85	23.44	RT	1	12	12			
3706+58.14	23.48	RT	1	12	12			
3706+93.59	20.98	LT	1	8			1	

FILE PATH = p:\388035\pmt\lsc\comon\lsc\local\p\ME\CD\000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\1\000\_CD\005\_Roadway\_Sheets\60W29\_sht-Schedule-01.dgn



D:\60W29-sht-Schedule-01.dgn	DESIGNED - JSL	REVISED -
USER NAME = BAWtor t	DRAWN - MNB	REVISED -
PLOT SCALE = 20.0000' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 10/29/2013	DATE - 10/30/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NONE SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. R.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	26
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	