

**EXISTING DRAINAGE STRUCTURE SCHEDULE**

STATION	OFFSET	CATCH BASINS TO BE ADJUSTED	MANHOLES TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	CATCH BASIN TO BE RECONSTRUCTED (SPECIAL) (SEE NOTE 1)	COMMENTS	
		EACH	EACH	EACH	EACH	EACH	EACH		
<b>PEORIA STREET</b>									
3700+03.04	0.00'		1					EX RIM EL = 592.97	PR RIM EL = 592.97
3700+03.25	72.63' RT	1						EX RIM EL = 592.33	PR RIM EL = 592.33
3700+96.17	108.43' LT	1						EX RIM EL = 593.349	PR RIM EL = 593.65
3702+19.67	17.09' RT		1					EX RIM EL = 594.48	PR RIM EL = 595.83
3702+48.07	56.16' RT				1				
3702+48.25	63.30' LT	1						EX RIM EL = 593.33	PR RIM EL = 593.33
3705+74.79	17.47' LT					1			
3705+76.67	16.74' RT					1			
3705+84.38	1.61' LT			1					
<b>EB I-290</b>									
343+73.70	42.40' RT				1				
344+98.10	35.00' RT		1					EX RIM EL = 577.21	PR RIM EL = 577.21
345+25.20	17.70' LT		1					EX RIM EL = 577.47	PR RIM EL = 577.47
345+25.50	37.30' RT						1		
345+36.90	42.90' RT				1				
345+39.80	26.20' LT	1						EX RIM EL = 577.21	PR RIM EL = 577.21
346+18.40	26.40' LT		1					EX RIM EL = 577.03	PR RIM EL = 577.03
<b>WB I-290</b>									
345+19.10	28.90' RT		1					EX RIM EL = 577.20	PR RIM EL = 577.27
345+27.40	28.80' RT	1						EX RIM EL = 577.19	PR RIM EL = 577.25
345+37.80	35.40' LT	1						EX RIM EL = 577.11	PR RIM EL = 577.11
<b>TOTALS</b>		<b>6</b>	<b>6</b>	<b>1</b>	<b>3</b>	<b>2</b>	<b>1</b>		

**NOTES:**

- SEE SPECIFICATIONS FOR A DESCRIPTION OF THIS WORK.
- STATION, OFFSET, AND ELEVATION FOR STRUCTURES LOCATED ALONG THE SINGLE FACE BARRIER WALL ARE GIVEN AT THE TOE OF THE WALL.

DRAINAGE AND UTILITY SHEET NO.	LOCATION	STORM SEWER REMOVAL	COMBINED SEWER REMOVAL			TRENCH BACKFILL	TELEVISION INSPECTION OF SEWER	TELEVISION INSPECTION OF SEWER, SPECIAL	COMBINED SEWERS TO BE CLEANED	COMBINED SEWERS TO BE CLEANED, SPECIAL	STORM SEWERS TO BE CLEANED	WATER MAIN REMOVAL, 12"
		FOOT	FOOT			CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
		10"	8"	12"	54"						10"	12"
1	PEORIA STREET		48	4	77	261.0	830	1,860	415	930		27
5, 7	WB I-290						288					
6, 8	EB I-290	9					224			112		
<b>TOTAL</b>		<b>9</b>	<b>48</b>	<b>4</b>	<b>77</b>	<b>261.0</b>	<b>1,342</b>	<b>1,860</b>	<b>415</b>	<b>930</b>	<b>112</b>	<b>27</b>

**NOTES:**

- ADDITIONAL TRENCH BACKFILL QUANTITY PROVIDED ON THE DRAINAGE AND UTILITY SCHEDULE FOR THE PROPOSED STORM SEWER AND COMBINED SEWER.
- THE QUANTITY PROVIDED FOR TELEVISION INSPECTION OF SEWER CONSIST OF WORK BEFORE AND AFTER CONSTRUCTION.

FILE PATH = p:\388035\pmt\lsc\comon\lme\local\p\wec\000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\000\_CAD\005\_Roadway\Sheets\60W29\_sht-Schedule-Drain-01.dgn



DI60W29-sht-Schedule-Drain-01.dgn	DESIGNED - JLV	REVISED -
USER NAME = BAW:tor t	DRAWN - JSL	REVISED -
PLOT SCALE = 20.0000' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 10/29/2013	DATE - 10/30/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DRAINAGE SCHEDULES**

SCALE: NONE SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	28
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	