

ROUTE: IL 62 (Algonquin Rd.) (Penny Road to West of Roselle Road) - Jointed Pavement							Precast
CROSS STREET		*STATION	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)
FROM	TO						
Penny Road		19+50	EB	1(INT)	12	6	72
		19+50	EB	2(INT)	12	6	72
		19+73	EB	1(INT)	12	18	216
		19+73	EB	2(INT)	12	6	72
		20+05	EB	1(INT)	12	6	72
		20+05	EB	2(INT)	12	6	72
Bridlewood Trail	Bridlewood Trail	25+25	EB	1	12	6	72
		29+55	EB	1	12	6	72
		29+55	EB	2	12	6	72
		31+35	EB	1	12	12	144
		31+35	EB	2	12	12	144
		32+51	EB	1	12	6	72
		32+51	EB	2	12	6	72
		34+95	EB	2	12	6	72
		34+95	EB	RT	11	6	66
		35+15	EB	1	12	6	72
		35+15	EB	2	12	6	72
		35+15	EB	RT	12	6	72
		35+73	EB	RT	12	6	72
		36+30	EB	1	12	10	120
		36+30	EB	2	12	10	120
		36+30	EB	RT	12	6	72
		37+06	EB	1	12	6	72
		37+06	EB	2	12	6	72
		37+98	EB	RT	12	6	72
		38+30	EB	2	12	20	240
		38+33	EB	3	12	15	180
		38+42	EB	1	12	6	72
		39+00	EB	RAD	7	7	49
		39+04	EB	RAD	9	25	225
		39+07	EB	2(INT)	12	6	72
Barrington Road	Barrington Road	39+25	EB	1(INT)	12	10	120
		40+65	EB	2	12	6	72
		40+92	EB	1	12	6	72
		40+92	EB	2	12	6	72
		44+63	EB	2	12	6	72
		54+86	EB	1	12	8	96
		54+86	EB	2	12	8	96
	Willow Creek Church Drive	55+26	EB	LT	16	6	96
Willow Creek Church Drive		56+48	EB	1	12	6	72
		56+48	EB	2	12	6	72
		60+19	EB	1	12	10	120
		60+19	EB	2	12	10	120
		62+82	EB	1	12	10	120
		62+82	EB	2	12	10	120
		63+24	EB	1	12	15	180
		63+24	EB	2	12	15	180
		64+23	EB	2	12	6	72
		64+41	EB	1	12	6	72
		64+41	EB	2	12	6	72
		64+71	EB	2	12	6	72
		65+81	EB	1	12	6	72
		65+81	EB	2	12	6	72
		66+43	EB	1	12	11	132
		66+43	EB	2	12	11	132
		67+35	EB	2	12	6	72
		68+95	EB	1	12	6	72
		68+95	EB	2	12	6	72
		72+70	EB	2	12	6	72
	Whispering Trails Drive	73+06	EB	LT	12	6	72
Whispering Trails Drive		74+35	EB	1	12	10	120
		74+35	EB	2	12	10	120
		80+64	EB	2	12	6	72
		87+85	EB	2	12	6	72
		89+08	EB	LT	16	15	240
		89+78	EB	1	12	17	204
		89+78	EB	2	12	17	204
		93+23	EB	1	12	6	72

ROUTE: IL 62 (Algonquin Rd.) (Penny Road to West of Roselle Road) - Jointed Pavement							Precast
							(continued)
CROSS STREET		*STATION	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)
FROM	TO						
		93+23	EB	2	12	6	72
		95+47	EB	1	12	6	72
		95+47	EB	2	12	6	72
		95+72	EB	1	12	6	72
		95+82	EB	2	12	13	156
		96+22	EB	1(INT)	12	6	72
		96+22	EB	2(INT)	12	6	72
	Huntington Blvd/Freeman Rd	96+24	EB	INT	14	6	84
Huntington Blvd/Freeman Rd		97+23	EB	1	12	10	120
		97+23	EB	2	12	10	120
		97+94	EB	1	12	6	72
		97+94	EB	2	12	6	72
		99+15	EB	1	12	6	72
		99+15	EB	2	12	6	72
		99+43	EB	1	12	6	72
		99+43	EB	2	12	6	72
		100+25	EB	LT	9	6	54
		100+75	EB	1	12	6	72
		100+75	EB	2	12	6	72
		101+12	EB	1	12	6	72
		101+12	EB	2	12	6	72
		101+27	EB	1	12	6	72
		101+27	EB	2	12	6	72
		101+27	EB	LT	11	6	66
		101+56	EB	1	12	6	72
		101+56	EB	2	12	6	72
		101+59	EB	LT	12	6	72
		102+88	EB	1	12	6	72
		102+88	EB	2	12	6	72
		102+88	EB	LT	12	6	72
		103+56	EB	2	12	32	384
		103+72	EB	1	12	16	192
		103+81	EB	LT	16	6	96
		104+01	EB	LT	16	6	96
		107+36	EB	2	12	6	72
		109+59	EB	LT	12	6	72
		112+53	EB	1	12	6	72
		112+53	EB	2	12	6	72
		114+46	EB	1	12	6	72
		114+46	EB	2	12	6	72
		114+68	EB	1	12	6	72
		114+68	EB	2	12	6	72
		116+47	EB	1	12	10	120
		116+47	EB	2	12	10	120
		118+74	EB	1	12	6	72
		118+74	EB	2	12	6	72
		120+96	EB	1	12	6	72
		120+96	EB	2	12	6	72
		121+45	EB	1	12	6	72
		121+45	EB	2	12	10	120
		121+66	EB	1	12	6	72
		121+66	EB	2	12	6	72
		125+42	EB	1	12	6	72
		125+42	EB	2	12	6	72
		125+42	EB	LT	12	6	72
		126+64	EB	1	12	6	72
		126+64	EB	2	12	6	72
		126+64	EB	LT	12	6	72
		126+84	EB	1	12	6	72
		126+84	EB	2	12	6	72
		126+84	EB	LT	12	6	72
		133+60	EB	2	12	6	72
		142+36	EB	1	12	7	84
		142+36	EB	2	12	7	84
	Lexington Drive	142+80	EB	LT	12	6	72

* STATIONING = APPROXIMATE WEST EDGE FOR EB LANES
APPROXIMATE EAST EDGE FOR WB LANES

FILE NAME =	USER NAME = PencePL	DESIGNED -	PLP	REVISED -	-
Default	Plot Scale = 100.0000' / in.	DRAWN -	PLP	REVISED -	-
	Plot Date = 11/8/2013	CHECKED -	-	REVISED -	-
		DATE -	-	REVISED -	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

IL 62 (ALGONQUIN ROAD)-PENNY ROAD TO WEST OF ROSELLE ROAD			
SCHEDULE OF QUANTITIES (PATCHING)			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
339	116(R&R-3)PCC-PP	COOK	29	6
CONTRACT NO. 60W56			ILLINOIS FED. AID PROJECT	