CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
				TRAFFIC SIGNAL 0021																			
				X	X	X	X	✓	✓	✓	✓	✓	URBAN ✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	
X8803088	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	63	9	11	2	4			2	3	23				2		2	2			3	
X8803090	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	10	3	2	2				1		1						1					
X8803110	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED, RETROFIT	EACH	3															3					
X8803120	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	2	2																			
X8803210	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	35	6	6	2	1				1	15				2						2	
X8803910	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	2							1		1											
X8880015	PEDESTRIAN PUSH-BUTTON, NON-LATCHING	EACH	81	14	19		4					25						6	4		4	5	
Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500																			

Ø0042

1 Rev. 12-30-13

CIVILTECH	USER NAME = jrt	DESIGNED - BRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JRT	REVISED -				2013-055TS	COOK	73	10
	PLOT SCALE = 40.0000 ' / in.	CHECKED - JJE	REVISED -					CONTRACT NO. 60X16		
	PLOT DATE = 12/2/2013	DATE - 12/02/2013	REVISED -		NO SCALE / SHEET NO. 6 OF 6 SHEETS / STA. / TO STA.		ILLINOIS FED. AID PROJECT			