

A,01 / C,01 / G,01 / C,02 / G,02 / G,03 / C,03 / C,04 / C,05 / G,04 / C,06 / G,05 / G,06 / G,07 / C,07 / C,08 / G,08 / C,09 / G,09

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																			
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	
				TRAFFIC SIGNAL																			
				0021																			
URBAN																							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8																			
67100100	MOBILIZATION	L SUM	1	1																			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																			
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	57	13	8	1	2	1	1	1	1	14	2	1	1	1	1	4	2	1	1	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1														1						
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1									1											
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	32	2	3				1			17	4			2			1	1			1
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	42		7			6	2			6	4	3	1			2		6	2		3
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	14		1							7	2		1					2	1		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	54	10	11		4	1	3			10	4		3			2	3			3	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	44		3			1	1			23	7	2	3					3		1	
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	4					4															
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	22		2			1	2			2	3		1			4	3	2	2		
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	47	6	15		4		1			6	4	4	1			4	1		1		

141



USER NAME = jrt	DESIGNED - BRD	REVISED -
PLOT SCALE = 40,0000 1/4"	DRAWN - JRT	REVISED -
PLOT DATE = 12/2/2013	CHECKED - JJE	REVISED -
	DATE - 12/02/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		
NO SCALE	SHEET NO. 3 OF 6 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS
	2013-055TS	COOK	73
			7
CONTRACT NO. 60X16			
ILLINOIS FED. AID PROJECT			