

SCHEDULE OF QUANTITIES

40600990	TEMPORARY RAMP			
<u>SQ_YD</u>	<u>LOCATION</u>			
23.3	STA 907 + 25	TO	907 + 70	
23.3	STA 915 + 80	TO	916 + 25	
23.3	STA 1093 + 33	TO	1093 + 78	
23.3	STA 1098 + 73	TO	1099 + 18	
11.1	STA 103 + 25	TO	103 + 70	
11.1	STA 108 + 80	TO	109 + 25	
11.1	STA 118 + 25	TO	118 + 70	
11.1	STA 120 + 32	TO	120 + 77	
<u>137.8</u>	TOTAL			

50100300	REMOVAL OF EXISTING STRUCTURE NO. 1			
<u>EACH</u>	<u>LOCATION</u>			
1	STATION 912 + 26			

50100400	REMOVAL OF EXISTING STRUCTURE NO. 2			
<u>EACH</u>	<u>LOCATION</u>			
1	STATION 119 + 49			

50100500	REMOVAL OF EXISTING STRUCTURE NO. 3			
<u>EACH</u>	<u>LOCATION</u>			
1	STATION 105 + 82			

542A0253 PIPE CULVERTS, CLASS A, TYPE 1 48"

<u>FOOT</u>	<u>LOCATION</u>
	Canyon Rd
<u>110.0</u>	Sta 119 + 63
110.0	TOTAL

542A0265 PIPE CULVERTS, CLASS A, TYPE 1, 60"

<u>FOOT</u>	<u>LOCATION</u>
15	STATION 1096 + 59 LT
<u>96</u>	STATION 105 + 93
111	TOTAL

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

<u>FOOT</u>	<u>LOCATION</u>					
39	STATION 908 + 87	TO	909 + 48	LT		
45	STATION 909 + 37	TO	909 + 99	RT		
<u>88</u>	STATION 1094 + 50	TO	1095 + 15	LT		
172	TOTAL					

54213450 END SECTIONS 15"

<u>EACH</u>	<u>LOCATION</u>
1	STATION 908 + 87 LT
1	STATION 909 + 48 LT
1	STATION 909 + 37 RT
1	STATION 909 + 99 RT
1	STATION 1094 + 50 LT
1	STATION 1095 + 15 LT
<u>6</u>	TOTAL

54260311 TRAVERSABLE PIPE GRATE

<u>FOOT</u>	<u>LOCATION</u>
66	STATION 912 + 26 LT/RT
<u>70.42</u>	STATION 1096 + 26 LT
17	STATION 1096 + 26 RT
20	STATION 105 + 93 LT
39.5	STATION 105 + 93 RT
95.5	STATION 119 + 49 LT
95.5	STATION 119 + 49 RT
<u>403.92</u>	TOTAL

54261360 CONCRETE END SECTION, STANDARD 542001, 60", 1:3

<u>EACH</u>	<u>LOCATION</u>
1	STATION 105 + 92

54262448 CONCRETE END SECTION, STANDARD 542006, 48", 1:4

<u>EACH</u>	<u>LOCATION</u>
2	STATION 119 + 63

54263460 CONCRETE END SECTION, STANDARD 542011, 60", 1:4

<u>EACH</u>	<u>LOCATION</u>
1	STATION 1096 + 26

X - FAP 650 & FAS 74

FILE NAME =	USER NAME = rundbladerr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 78 / CANYON RD. SCHEDULE OF QUANTITIES	F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\rundbladerr\d0232736	D201310-sh-t-schedule.dgn	DRAWN -	REVISED -			X	104T-3	97	21
	PLOT SCALE = 80.0000' / in.	CHECKED -	REVISED -						
	PLOT DATE = Thu Oct 10 13:29:39 2013	DATE -	REVISED -						
						SCALE: _____	SHEET _____	OF _____	SHEETS _____
						STA. _____	TO STA. _____	ILLINOIS FED. AID PROJECT	
						CONTRACT NO. 64F74			