

PAVEMENT WIDENING SCHEDULE										
LOCATION	PAVED SHOULDER REMOVAL		PAVEMENT REMOVAL		SUB-BASE GRAN. MATL, TYPE A 12"		HOT-MIX ASPHALT BASE COURSE, 9"		BITUMINOUS MATERIALS (PRIME COAT)	
	RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	RURAL	URBAN
	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	POUND	POUND
RT. STA. 1373+00 TO STA. 1419+00 - STAGE IA 1.) THRU STAGE IA 3.)	----	1166.9	----	152.7	----	7041.8	----	3051.4	----	8238.8
LT. STA. 1412+50 TO STA. 1418+25 - STAGE IA 4.)	----	214.2	----	----	----	958.3	----	415.3	----	1121.3
RT. STA. 1414+00 TO STA. 1416+25 - STAGE IA 5.)	----	150.0	----	----	----	375.0	----	162.5	----	438.8
LT. STA. 1398+50 TO STA. 1404+00 - STAGE IA 6.)	----	206.5	----	----	----	916.7	----	397.2	----	1072.5
RT. STA. 1400+50 TO STA. 1402+00 - STAGE IA 7.)	----	100.0	----	----	----	250.0	----	108.3	----	292.5
RT. STA. 1365+50 TO STA. 1373+00 - STAGE IB	----	207.3	----	635.4	----	1250.0	----	541.7	----	1462.5
RT. STA. 1352+00 TO STA. 1365+50 - STAGE IC	----	202.9	----	247.2	----	2250.1	----	975.0	----	2632.5
RT. STA. 1321+50 TO STA. 1352+00 - STAGE ID	706.8	----	----	----	5083.3	----	2202.8	----	5947.5	----
RT. RAILROAD CROSSING TO STA. 1321+50 - STAGE IE	394.3	----	373.5	----	1560.8	----	496.6	----	1340.7	----
RT. STA. 1419+00 TO STA. 1489+79.11 - STAGE IF	----	2232.0	----	510.6	----	10809.2	----	4584.0	----	12376.8
LT. RAILROAD CROSSING TO STA. 1354+00 - STAGE IIA	1239.8	----	----	----	6884.6	----	2843.8	----	7678.2	----
LT. STA. 1354+00 TO STA. 1398+50 - STAGE IIB	----	1597.4	----	1379.3	----	7416.7	----	3213.9	----	8677.5
LT. STA. 1404+00 TO STA. 1412+50 - STAGE IIB	----	319.5	----	----	----	1416.4	----	613.8	----	1657.2
LT. STA. 1418+25 TO STA. 1489+79.11 - STAGE IIC	----	1960.1	----	661.3	----	10928.4	----	4631.1	----	12504.0
S5000WROAD	----	----	----	----	518.0	----	532.4	----	1437.5	----
N4000WROAD	----	----	----	----	----	510.9	----	537.2	----	1450.5
RAYMOND DRIVE	----	----	----	----	----	203.3	----	228.1	----	615.8
S4080WROAD	----	----	----	----	----	190.9	----	198.4	----	535.8
S4000WROAD	----	----	----	----	----	568.2	----	588.3	----	1588.3
MONTEREY DRIVE	----	----	----	----	----	235.1	----	217.3	----	566.8
N3290WROAD	----	----	----	----	----	800.1	----	728.3	----	1966.3
S3160WROAD	----	----	----	----	----	160.7	----	177.6	----	479.6
S3120WROAD	----	----	----	----	----	125.2	----	177.1	----	478.2
N2750WROAD	----	----	----	----	----	510.4	----	536.8	----	1449.5
S3000WROAD	----	----	----	----	----	512.6	----	538.7	----	1454.6
N1790WROAD	----	----	----	----	----	230.3	----	304.6	----	822.4
SUBTOTALS	2340.8	8356.7	373.5	3586.5	14046.7	47660.4	6075.5	22926.7	16403.9	61902.1
TOTAL		10698		3960		61707		29002		78306

PAVEMENT PATCHING SCHEDULE			
LOCATION	CLASS D PATCHES		
	TYPE II, 9"		TYPE IV, 9"
	RURAL	URBAN	URBAN
	SQ YD	SQ YD	SQ YD
LT STA 1337+50 TO STA 1337+58	10.7	----	----
RT STA 1337+50 TO STA 1337+58	10.7	----	----
LT STA 1344+72 TO STA 1344+78	8.0	----	----
RT STA 1344+72 TO STA 1344+78	8.0	----	----
LT STA 1442+04 TO STA 1442+12	----	10.7	----
RT STA 1442+04 TO STA 1442+12	----	10.7	----
LT STA 1401+17 TO STA 1401+57	----	8.9	----
RT STA 1401+17 TO STA 1401+57	----	----	97.8
LT STA 1415+30 TO STA 1415+70	----	8.9	----
RT STA 1415+30 TO STA 1415+70	----	----	97.8
LT STA 1465+88 TO STA 1466+12	----	----	32.0
RT STA 1465+88 TO STA 1466+12	----	----	32.0
SUBTOTALS	37	39	
TOTAL		76	260

TEMPORARY RAMP SCHEDULE*			
LOCATION	TEMPORARY RAMP		TEMPORARY RAMP
	RURAL	URBAN	
	SQ. YD.	SQ. YD.	
MAINLINE			
RAILROAD CROSSING	42	----	
STA 1489+79.11	----	35	
SIDERROADS			
S 5000W ROAD	22	----	
N 4000W ROAD	----	54	
RAYMOND DRIVE	----	44	
S 4080W ROAD	----	37	
S 4000W ROAD	----	54	
MONTEREY DRIVE	----	39	
N 3290W ROAD	----	57	
S 3160W ROAD	----	36	
S 3120W ROAD	----	46	
N 2750W ROAD	----	57	
S 3000W ROAD	----	57	
N 1790W ROAD	----	37	
SUBTOTALS	64	554	
TOTAL		618	

* RAMP AREAS MAY INCLUDE MULTIPLE RAMPS REQUIRED FOR STAGE CONSTRUCTION

MISCELLANEOUS REMOVAL SCHEDULE					
LOCATION	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	MEDIAN REMOVAL		PAVED DITCH REMOVAL
	URBAN	URBAN	RURAL	URBAN	URBAN
	FOOT	SQ FT	SQ FT	SQ FT	FOOT
STA 1312+11.5 TO STA 1312+33.7, RT	----	----	106	----	----
STA 1313+46.2 TO STA 1313+79.4, RT	----	----	198.0	----	----
STA 1314+20.3 TO STA 1314+99.2, RT	----	----	530.0	----	----
STA 1315+36.4 TO STA 1315+57.2, RT	----	----	121.0	----	----
STA 1353+30.4 TO STA 1354+45.0, RT	----	----	571.0	----	----
STA 1354+83.5 TO STA 1355+06.1, RT	----	----	107.0	----	----
STA 1358+25.6 TO STA 1359+02.7, LT	----	----	----	----	78.0
STA 1363+01.2 TO STA 1363+37.4, RT	----	----	----	----	36.0
STA 1363+71.8 TO STA 1364+46.6, RT	----	----	----	----	75.0
STA 1374+35.5 TO STA 1378+37.5, LT	----	1471.0	----	----	----
STA 1458+80.1 TO STA 1460+24.9, RT	----	----	----	717.0	----
STA 39+00 TO STA 39+56, LT & RT - RAYMOND DRIVE	106.0	----	----	----	----
SUBTOTALS			1633	717	
TOTAL	106	1471	2350		189

SURFACE REMOVAL SCHEDULE			
LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"
	RURAL	URBAN	URBAN
	SQ YD	SQ YD	SQ YD
STA 1310+90.89 TO STA 1312+10	----	366.9	----
STA 218+54.43 TO STA 218+70.03 (S5000W ROAD)	----	35.9	----
STA 39+00 TO STA 39+31.76 (RAYMOND DRIVE)	112.0	----	----
STA 48+46 TO STA 48+68.31 (S4080W ROAD)	43.9	----	----
STA 71+35.51 TO STA 71+69 (MONTEREY DRIVE)	74.7	----	----
STA 88+50 TO STA 89+17.83 (S3160W ROAD)	120.1	----	----
STA 130+71.81 TO STA 131+31.37 (N1790W ROAD)	117.8	----	----
STA 1484+32 TO STA 1484+92	344.5	----	----
STA 1484+92 TO STA 1489+79.11	----	----	3594.7
SUBTOTALS	813.0	402.8	
TOTAL		1216	3595

STRIP REFLECTIVE CRACK CONTROL SCHEDULE			
LOCATION	STRIP REFLECTIVE CRACK CONTROL		
	RURAL	URBAN	
	FOOT	FOOT	FOOT
MAINLINE			
RT STA 1310+36.12 TO STA 1355+71	4535	----	----
RT STA 1355+71 TO STA 1489+79.11	----	----	13408
LT STA 1311+08.71 TO STA 1355+71	4462	----	----
LT STA 1355+71 TO STA 1489+79.11	----	----	13408
SUBTOTALS	8997		26816
TOTAL			35813