

80% FED. / 20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY 0004 RURAL	BOX CULVERT 0011 PROP. S. N. 050-2055	BOX CULVERT 0040 PROP. S. N. 050-2056	BOX CULVERT 0011 PROP. S. N. 050-2057
50105220	PIPE CULVERT REMOVAL	FOOT	48	48			
50200100	STRUCTURE EXCAVATION	CU YD	41.2				41.2
50300225	CONCRETE STRUCTURES	CU YD	14.6				14.6
50500505	STUD SHEAR CONNECTORS	EACH	54				54
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	53,970				53,970
51500100	NAME PLATES	EACH	3		1	1	1
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2		2		
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2			2	
54003000	CONCRETE BOX CULVERTS	CU YD	227				227
54010909	PRECAST CONCRETE BOX CULVERTS 9' X 9'	FOOT	114			114	
54011007	PRECAST CONCRETE BOX CULVERTS 10' X 7'	FOOT	96		96		
54213453	END SECTIONS 18"	EACH	4	4			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	3.5				3.5
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	680	680			

Rev.

*specialty items

FILE NAME *	USER NAME * #USER#	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 786	SECTION (110)BR-1,2,3	COUNTY LASALLE	TOTAL SHEETS 69	SHEET NO. 5
#FILE#	PLOT SCALE * #SCALE#	DRAWN - _____	REVISED - _____					SCALE: _____	SHEET _____	OF _____	SHEETS	STA. _____
#MODELNAME#	PLOT DATE * #DATE#	CHECKED - _____	REVISED - _____		[ILLINOIS] FED. AID PROJECT							
		DATE - _____	REVISED - _____									