

PAVEMENT MARKING SCHEDULE										
LOCATION		DISTANCE	PAINT PVT MK 4"	PAINT PVT MK 6"	TEMP MARK 4"	TEMP MARK 6"	SHORT-TERM MARK	WORK ZONE PAVT MARK REM	RAISED REFLECTIVE PVMT MARKERS	REMOVAL RAISED REFLECTIVE PVT MARKERS
STA		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO. FT.	EACH	EACH
050-0143										
311+00	TO 317+00	600	1200	150	1200	150	180	60	8	8
(2) DOUBLE APPLICATION			1200	150						
050-0143 SUBTOTAL			2400	300	1200	150	180	60	8	8
050-0156										
366+50	TO 372+50	600	1200	150	1200	150	180	60	8	8
(2) DOUBLE APPLICATION			1200	150						
050-0156 SUBTOTAL			2400	300	1200	150	180	60	8	8
050-0072										
442+25	TO 449+50	725	1450	181	1450	181	218	72	9	9
(2) DOUBLE APPLICATION			1450	181						
050-0072 SUBTOTAL			2900	363	1450	181	218	72	9	9
GRAND TOTAL		1925	7700	963	3850	481	578	192	24	24

(1) R.E. TO VERIFY NO PASSING ZONES PRIOR TO MILLING OPERATION
(2) PAINT MUST BE DONE IN A DOUBLE APPLICATION

SEEDING SCHEDULE									
LOCATION	LANE	SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	HEAVY DUTY EROSION CONTROL BLANKET	TEMP DITCH CHECKS	PERIMETER EROSION BARRIER*	TEMP EROSION CONTROL SEEDING
STA TO STA		ACRE	POUND	POUND	POUND	S.Y.	FOOT	FOOT	POUND
S.N. 050-0143									
STA 311+00 TO STA 314+00 LT	NB	0.20	18	18	18	968	30	30	40
STA 311+00 TO STA 314+00 RT	SB	0.20	18	18	18	968	30	30	40
STA 314+00 TO STA 317+00 LT	NB	0.20	18	18	18	968	30	30	40
STA 314+00 TO STA 317+00 RT	SB	0.20	18	18	18	968	30	30	40
S.N. 050-0143 SUBTOTAL		0.80	72	72	72	3872	120	120	160
S.N. 050-0156									
STA 366+50 TO STA 369+50 LT	NB	0.18	16	16	16	871	30	30	36
STA 366+50 TO STA 369+50 RT	SB	0.12	11	11	11	581	30	28	24
STA 369+50 TO STA 372+50 LT	NB	0.20	18	18	18	968	30	30	40
STA 369+50 TO STA 372+50 RT	SB	0.19	17	17	17	920	30	28	38
S.N. 050-0156 SUBTOTAL		0.69	62	62	62	3340	120	116	138
S.N. 050-0072									
STA 442+25 TO STA 445+50 LT	NB	0.17	15	15	15	823	30	51	34
STA 442+25 TO STA 445+50 RT	SB	0.22	20	20	20	1065	30	53	44
STA 445+50 TO STA 449+50 LT	NB	0.24	22	22	22	1162	30	54	48
STA 445+50 TO STA 449+50 RT	SB	0.31	28	28	28	1500	30	49	62
S.N. 050-0072 SUBTOTAL		0.94	85	85	85	4550	120	207	188
GRAND TOTAL		2.4	219	219	219	11761	360	443	486

*PLACE ALONG CREEK, SOUTH SIDE AND NORTH SIDE