

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				0021 SAFETY	0021 TRAFFIC SIGNAL	0021 OVERHEAD LIGHTING	0004 ROADWAY	0004 ROADWAY	0004 ROADWAY	
				90% FED 10% STATE	90% FED 6.7% STATE 3.3% CITY	100% CITY	80% FED 20% STATE	80% STATE 20% CITY	100% STATE	
X 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	648		60	588				
X 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	3			3				
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1190.5		1190.5					
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	575.5		575.5					
X 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1210.5		1210.5					
X 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	458		458					
X 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1		1					
X 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1					
X 87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	2		2					
X 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3					
X 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	37		37					
X 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3		3					
X 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		3					
X 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1		1					

X SPECIALTY ITEM

FILE NAME :	USER NAME :	DESIGNED -	REVISED -
c:\pwork\p\p\dot\acbrejgs\80318674\046	n70-shi-cover.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 1/ in.	CHECKED -	REVISED -
	PLOT DATE = 10/16/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6558	10N	PEORIA	120	10
CONTRACT NO. 68A70				
ILLINOIS FED. AID PROJECT				